

SURVEY & REMONUMENTATION

MAY 05 1997

COMMISSION

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Allegan County	Located in	Corner Code #
	CASCO	L-13
	1 N 17 W	
1. Public Land Survey	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

1994 DEC 16 AM 9:56
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN
George J. Mitchell

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

George J. Mitchell November 4, 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
L-13


SEE BACK OF SHEET

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 10-11-94
COUNTY REP. *Paul J. ...*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13
FOUND ROAT SPIKE FROM OLD WITNESSES AND ACCEPTED SPIKE AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

CENTERLINE OF NORTH BOUND LANE OF BLUE STAR HIGHWAY - WEST 70.1'
EAST EDGE OF NORTH BOUND LANE OF BLUE STAR HIGHWAY - WEST 58.7'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13
REPLACED SPIKE WITH 3/4" X 24" PIN WITH ALLEGAN CO. REMON CAP.
Chisled "x" in top of concrete headwall AZ. 05° 30.81'
A.C. remon tag & nail in NW side of Power Pole AZ. 235° 36.07'
NW Corner of Frame House 4' up from ground AZ. 150° 71.57'
A.C. remon tag & nail in SE side of Power Pole AZ. 210° 58.79'

Signed by *George J. Mitchell* Date *November 4, 1994*
Surveyor's Michigan License No. *19618*

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1973
REVISED MAY 24, 1975
REVISED JAN., 1983

CORNER HISTORY

L-13. T1N, R17W
S 1/4 POST, SECTION 36
WEST CASCO

6/9/1827 WILLIAM BROOKFIELD- ORIGINAL CORNER SET
7" BEECH N35E 7 LKS
7" BEECH N59W 42 LKS
CORNER SET 40 CH WEST OF SE COR &
40 CH EAST OF SW CORNER.

05/1959 MDOT - CZUBAK - BOAT SPIKE OVER IRON
27" MAPLE N45E 35.75'
24" MAPLE S10W 26.85'
25" MAPLE S52W 46.15'
E. EDGE NORTH BOUND US31 - WEST 57.15'

WIGHTMAN MOORED CARD FILE - SAME AS ABOVE

05/1977 D.A. RATEKIN - SAME AS ABOVE

UNKNOWN FD BOAT SPIKE
EXISTING CENTER OF BASELINE ROAD - SOUTH 1.5'
30" MAPLE N40E 35.45'
30" MAPLE N25E 62.65'
POWER POLE S35W 58.94'
E. EDGE N. BOUND SLAB WEST 58.5

03/1979 MITCHELL FD BOAT SPIKE
POWER POLE SSW 59.75
30" MAPLE NNE 35.05
CL N. BOUND LANE BLUE STAR - WEST 70.30'

06/1991 MITCHELL SAME AS ABOVE
MEASURED 2621.84 NORTH TO CENTER
MEASURED 2631.16 WEST TO SW COR.

09/20/94 MITCHELL FOUND BOAT SPIKE
CENTER OF N. BD LANE WEST 70.1'
EAST EDGE N. BD LANE WEST 58.7'

SURVEY &
REMONUMENTATION

DEC 15 1995

COMMISSION