

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|--|----------------------------|---|
| <u>Allegan County</u> <small>(County)</small> | Located in: Martin Twp. | Corner Code ## B-1 |
| 1. Public Land Survey | T <u>2N</u> R <u>11W</u> | <u>N$\frac{1}{2}$ Sec. 6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

97 JAN 22 PM 1:26
 REGISTERED
 ALLEGAN COUNTY
 FILING OFFICE
 FILED

Register of Deeds Stamp & File Number

I, Robert Jonker, in a field survey on July 09, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
 Corner not set in GLO survey LCRC 3-271, 1980, Ratekin
 Witness card - 1" Iron
 Old wit. map - $\frac{1}{4}$ post on N. line Sec.6, T. pole SE 36.1'
 a stone - "X" on S. side Fe. post S 33'
 24" Ch. S 65.2'
 P. pole NE 75.6'

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 24" standard capped Allegan County monument in mon. box on twp. line per witnesses by Jonker in 1993.

A-1, T2N, R13W, West 3182.20'
 C-1, T2N, R13W, East 2689.67'

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Approved by the Allegan County Remonumentation Peer Group on July 9, 1996.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 7-9-96

C. Description of monument for corner and accessories established to perpetuate locating ~~HOODS~~ of the corner: *Robert J. Jonker*
 Standard Allegan County Monument in mon. box

S $\frac{1}{4}$ Sec.31, Wayland Twp., West 141.78'
 Nail & Tag top of fence post N 37° E 43.31'
 Nail & Tag top of fence post N 24° W 40.92'
 Nail & Tag NE side P. pole S 45° E 46.38'
 Nail & Tag W. side 31" W. Ch. S 06° W 63.30'
 Closing corner 0.35' North, not in.
 on fence & tree row to South



Signed by Robert J. Jonker Date November 26, 1996
 Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

B-1 MARTIN TWP.

Part "A." continued:

Ratekin (cont'd)

Found iron gone & set 1" iron 141.63' E
of S $\frac{1}{2}$ Sec. 31, Wayland Twp. per prior surveys

Took new witnesses

Nail E. face 22" W. Cherry South 63.47'
PK Nail NW face p. pole S 45° E 46.15'
C/L 124th Avenue North 1'
1" Iron West 141.63'

Jonker, 1993

Found 1 $\frac{1}{2}$ " Steel pipe 0.35' N of twp. line
Set 3/4" x 24" std. capped county mon. on twp. line, closing corner 0.35' N

Took witnesses

N & T on twp. fe. post Az. 37° 43.39'
N & T on twp. fe. post Az. 336° 41.00'
N & T on NE side P. pole Az. 135° 46.38'
N & T on W. side 30" W. Ch. Az. 186° 63.30'
C/L #-W road North 1'
On tree & fence row to South
 $\frac{1}{2}$ cor. to Wayland Twp. West 141.8'