

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan County
(County)

Located In: Martin Twp. Corner Code ##

- | | | | |
|------------------------------------|---|---|------------|
| 1. Public Land Survey | T | R | |
| | T | R | <u>11W</u> |
| | T | R | <u>2N</u> |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

C-1
NE Cor. Sec. 6

97 JAN 22 9 11 AM '96
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert Jonker, in a field survey on July 09, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 75.74 ch. Int. N. line 1.5 links E. of post
 Birch 6 S 71E 30. LCRC #2-128, Ratekin, 1973
 Do 6 S 53W 60. Part A - witness card - iron in BT
 Old County Surveyor notes, Part B - found 1 1/2" iron
 stone at true corner Part C - C/L old US-131 W. 181'
 NW cor. porch S 30° W 55.25'
 SE cor. ret. wall N 60° W 59.03'
 NW cor. conc. post on W. end ret. wall
 N 45° E 37.45'
- No info in M.D.O.T. R/W book.

(OVER)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 3/4" x 24" std. capped Allegan County monument in mon. box on twp. line per wit. for LCRC as recorded, and Jonker witnesses from 1993.

APPROVED REMONUMENTATION CORNER
 P.A. 74 OF 1970
 ALLEGAN COUNTY
 DATE APPROVED: 11-26-96
 COUNTY REP. Paul L. [Signature]


Accepted as the best available evidence of the position of the original corner

Approved by the Allegan County Remonumentation Peer Group on Nov. 26, 1996.

B-1, T2N, R11W, West 2689.67'
 D-1, T2N, R11W, East 2590.52'

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Allegan County monument on township line.
 PK Nail SW side P. pole S 63° E 64.23'
 PK Nail SW side P. pole S 26° E 33.52'
 SE cor. block bldg. N 17° E 77.65'
 NE cor. hse. #994, fndn. S 11° W 56.91'
 Nail & Tag N. side P. pole S 76° W 81.70'



Signed by Robert J. Jonker
 Robert J. Jonker, P.S. 21572
 Surveyor's Michigan License No. _____

Date November 26, 1996

LIBER 0005 PAGE 479

C-1 MARTIN TWP.

Part "A." cont'd

MAY 22 1997

LCRC #3-105 - M.V.K., 1976 - 1½" solid iron
 PK in SW side T. pole SSE 33.6'
 Sq. Spk. W. side Maple S 44.25'
 PK N'ly side P. pole WSW 81.80'
 SE cor. conc. block Bldg. NNE 77.60'
 PK NE side P. pole ESE 64.24'
 C/L BT N 2'
 C/L old US-131 W 182.4'

Jonker, 1993

Found 1" x 20½" solid bar in mon. box
 Replaced with ¾" x 24" std. capped county monument
 Fd. PK SW side P. pole Az. 117° 64.23'
 Fd. PK Sw side P. pole Az. 154° 33.52'
 SE cor. block bldg. Az. 17° 77.62'
 NE cor. hse. fndn. Az. 191° 56.91'
 Nail & Tag N. side P. pole Az. 256° 81.68'

FILED

97 JAN 22 11 1:26

Joyce A. ...
 REGISTER OF DEEDS
 ALLEGANY COUNTY, PA.