

COMMISSION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

97 JAN 22 PM 1:27

FILED

For corners in

ALLEGAN
(County)

Located In:

Corner Code #

1. Public Land Survey

T2N R 11W D-9
T__R S 1/4 COR
T__R SEC 20
T__R N 1/4

2. Property Controlling
in Section

S__T__R SEC 29
S__T__R MARTIN TWP.

3. Miscellaneous
Property in Sec.

S__T__R
S__T__R

4. Lot No. _____, Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BERYL M. JONES, in a field survey on 12/10, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-9 40.16 CHAINS EAST OF C-9 GLO SET 1/4 SECTION POST NO WITNESS'S SHOWN, CORNER IDENTIFIED AS 5" BIRCH
LCR 1" IRON IN MON BOX 4/18/72 D. RATEKIN L.1, PAGE 228
LCR BOAT SPIKE 1/22/74 D. RATEKIN L. 2, PAGE 257 (IS ERRONEOUS)
LCR IRON (NO SIZE) 11/8/74 D. RATEKIN L. 2, PAGE 421
SURVEY CERTIFICATE 1" IRON 3/6/72 D. RATEKIN (SAME AS 4/18/72 LCR RATEKIN L.1, PAGE 228)
ACT 132 SURVEY 1" IRON 3/25/90 J. DILLINGHAM (SAME AS 4/18/72 LCR, D. RATEKIN L.1, PAGE 228)
SURVEY SKETCH NOT IDENTIFIED 7/21/89 R. MOORED, NO WITNESSES
MCDUGAL SKETCH SHOWS IRON, NO SIZE, 1918 ML 9' WEST OF RAIL
ASSESSORS PLAT VILLAGE OF MARTIN, SHOWN, NO IDENTIFICATION OR DISTANCE TIES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9 FOUND 1" IRON IN MON BOX
ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITIN OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-10-96
COUNTY REP. Beryl M. Jones

APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON DECEMBER 10, 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-9 REMOVED 1" IRON, REPLACED WITH ALLEGAN CO. REMONUMENT
N.55° E SW COR BRICK BUILDING 53.60'
S 68° W POWER POLE 53.00'
N 62° W POWER POLE 53.00'
N 35° W SE COR BLOCK BUILDING 72.20'
S 25° E PK IN R.R. TIE 22.10

Signed by Beryl M. Jones Date 12/10/96
Surveyor's Michigan License No. 23514



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

0005 PAGE 483