

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan County</u> <small>(County)</small>	Located in: Martin Twp.	Corner Code # <u>E-1</u>
1. Public Land Survey	T <u>2N</u> R <u>11W</u>	<u>NE Cor. Sec. 5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

97 JAN 22 PM 1:21
 FILED
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	14	15	16	17	18						
7												
8	19	20	21	22	23	24						
9												
10	25	26	27	28	29	30						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on July 09, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

74.52 Ch. Int. N. line 128 links E. (84.48') of std. corner
 W. Oak 12 S 47 E 50
 Maple 12 S 22 W 60

1875 survey - Hicks - stake & stone

LCRC #2-128, Ratekin, 1973
 Part A - Nothing
 Part B - Set 1" iron
 Part C - Took witnesses
 NE cor. hse. fndn. S 30° W 92.43'
 Nail - P. pole S 30° W 33.42'
 Nail - P. pole N 60° W 75.33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" x 20 1/2" iron in mon. box
 Removed and replaced with 3/4" x 36" standard capped Allegan County monument.
 Also moved 0.08' North onto the twp. line.

D-1, T2N, R11W, West 2573.13'
 F-1, T2N, R11W, East 2667.47'

APPROVED REMONUMENTATION CORNER
 P.A. 343 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-26-96
 COUNTY REP. Robert Jonker

Accepted as a careful & faithful reestablishment of the position of the original corner.


Approved by the Allegan County Remonumentation Peer Group on Nov. 26, 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Allegan County standard capped monument

NW corner of stone house fndn. S 08° E 80.16'
 Nail & Tag - E. side P. pole S 36° W 33.28'
 Nail & Tag - N. side P. pole N 65° W 75.42'
 Nail & Tag - E. side 24" Tw. tree N 21° E 70.26'
 SE cor. Sec. 32, Wayland Twp. West 84.48'

Nail & tags are Allegan Co. Remon. tags.



Signed by Robert J. Jonker Date November 26, 1996
 Robert J. Jonker, P.S. 21572
 Surveyor's Michigan License No. _____