

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY, MI
James Le...

00 FEB - 1 11 8 48

FILED
LDR00007 PAGE 373

SECTION

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T....2N R...11W	E-5 MORTON TWP.
SEC. COR COMMON TO SEC'S. 8, 9, 16, 17	T..... R.....
	T..... R.....
	T..... R.....
2. Property Controlling in section	S.....T.....R.....
	S.....T.....R.....
3. Miscellaneous Property in Sec.	S.....T.....R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

REGISTER OF DEEDS STAMP & FILE NUMBER

I, Raymond Moored in a field survey on May 11, 1999, do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
E-5

SEE BACK OF SHEET FOR CORNER HISTORY



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 FOUND 1" PIPE IN MON. BOX.
CHERRY TREE NE 33.5' AND MAPLE TREE NW 32.0' REMAIN

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON W/CAP IN MON BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX

FD NAIL IN NE SIDE OF P POLE	S 45E	47.72'
FD NAIL IN NW SIDE 28 INCH CHERRY	N 40E	33.75'
FD NAIL IN NE SIDE 28 INCH MAPLE	N 40W	31.92'
1/2 INCH IRON W / CAP	N	33.0'
TOP C/L TCB	N 70E	62.80'
IN C/L ROAD	E-W-S	

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED MAY 11, 1999
COUNTY REP. [Signature]

Raymond Moored

Date 12/13/99

Surveyors License No. 26463

RE

MAR 07 2000

SECTION

GOVERNMENT CORNER HISTORY
E-5
TOWN 2 NORTH, RANGE 11 WEST,
MARTIN TOWNSHIP, ALLEGAN COUNTY, MI

11/10/00 / PAGE 3 / 15

1. GLO NOTES STATE SET QUARTER SECTION POST
 B ASH 12 INCHES S 61 W 34
 BIRCH 10 INCHES N 101/2 E 42

2. H. McDOUGAL, CO. SURVEYOR, JUNE 9-13, 1898
 STONE FOR CORNER - NO WITNESSES

3. M.D.N.R. LATE 1950'S
 SURVEY OF PUBLIC FISHING SITE FOR LAKE 16 NOTES CORNER
 OBLONG STONE MARKED X
 BROKEN BRICK
 IRON PIN 81/2 INCHES TAPERING FROM 1 1/2 INCHES TO 1 INCH IN DIAM.
 WITNESSES FROM D. ALLEN, ALLEGAN CO. SURVEYOR NOTES
 MAPLE 20 SW 60.5. FEET
 MAPLE 3 NW 33 FEET
 NEW WITNESSES:
 MAPLE 28 S 67°W 61.5 FEET
 DO 18 N 37°W 33.1 FEET

4. D.A. RATEKIN CO. SURVEYOR 1960'S
 SECTION CARD NOTES 1/2 INCH IRON PIPE
 CONCRETE FENCE POST S 45° E 39.1 FEET
 STEEL FENCE POST NW 29.8 FEET
 STREET SIGN NW 26.5 FEET
 24 INCH CHERRY N 40° E 33.5 FEET
 26 INCH MAPLE N 40° W 32.0 FEET
 10 INCH WALNUT N 55° W 54.0 FEET

5. D.A. RATEKIN, CO. SURVEYOR 1973
 SECTION CARD NOTES 1/2 IRON PIPE
 CONCRETE CORNER POST S 45°E 39.2 FEET
 24 INCH CHERRY N 40°E 33.5 FEET
 26 INCH MAPLE N 40°W 32.0 FEET
 10 INCH WALNUT N 55°W 54.0 FEET

6. L.C.R.C. RECORDED BY D.A. RATEKIN 1974
 NOTES WITNESSES SAME AS ITEM #2 AND ITEM #3

7. D.A. RATEKIN, CO. SURVEYOR 1960'S
 BOUNDARY SURVEY OF LAKE DOUBLE EIGHT NOTES CORNER
 WITNESSES SAME AS ITEM # 3

8. D.A. RATEKIN, CO. SURVEYOR 1979
 SURVEY FOR GEO. RANKENS NOTES CORNER
 WITNESSES SAME AS ITEM #3

9. WIGHTMAN-MOORED, INC. 1993
 MORTGAGE SURVEY NOTES CORNER
 NO WITNESSES NOTED