

RF

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

LIBR0007 PAGES 75
FILED

00 FEB - 1 AM 8:48

REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

SECTION

FOR CORNERS IN:
ALLEGAN COUNTY

1. Public Land Survey

LOCATED IN: T..2N.. R.11W..

CORNER CODE # E-6
MARTIN TWP.

T..... R.....

T..... R.....

T..... R.....

2. Property Controlling in section S.....T.....R.....

S.....T.....R.....

3. Miscellaneous Property in Sec. S.....T.....R.....

4. Lot No....., Recorded Plat.....

5. Private Claims.....

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	-	5	-	4	-	3	-	2	-	1		
3													
4	7	-	6	-	9	-	10	-	11	-	12		
5													
6	16	-	17	●	16	-	15	-	14	-	13		
7													
8	19	-	20	-	21	-	22	-	23	-	24		
9													
10	30	-	29	-	28	-	27	-	26	-	25		
11													
12	31	-	32	-	33	-	34	-	35	-	36		
13													

I, Raymond Moored in a field survey on May 11, 1999, do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990

ALLEGAN COUNTY

DATE APPROVED MAY 11, 1999

COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

E-6 FOUND 1 1/4" PIPE IN C/L GRAVEL ROAD PER # 3 ABOVE. 30" MAPLE EAST 20.56' REMAINS (TREE IS DEAD)

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

E-6

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP

FD NAIL NE SIDE 24 INCH MAPLE S 37°E 36.75'

FD NAIL S SIDE 12 INCH WALNUT E 51.64'

FD NAIL NW SIDE 14 INCH CHERRY N 36°E 51.87'

FD NAIL SW SIDE 28 INCH CHERRY N 39°W 47.50'

TOP C/L TCB N 42°W 43.35'

IN C/L GRAVEL ROAD
ON OCCUPATIONAL LINE TO EAST

[Signature: Raymond Moored]

Date 12/13/99

Surveyors License No. 26463

PAGE 1 of 2



RF

MAR 07 2000

SECTION

LIBRO 007 PAGES 76

GOVERNMENT CORNER HISTORY
E-6
TOWN 2 NORTH, RANGE 11 WEST,
MARTIN TOWNSHIP, ALLEGAN COUNTY, MI

1. GLO NOTES SET QUARTER POST
WITNESSES W. OAK 14 INCH S 14 W 49 FEET
DO 10 INCH N 1 E 44 FEET
2. H. Mc DOUGAL CO. SURVEYOR 1898
NOTES STATE A STONE WITH X WAS SET AS CORNER
3. D.A. RATEKIN CO. SURVEYOR WITNESS CARD
SECTION CARD NOTES STONE WITH X
12 INCH MAPLE NW 61.3'
26 INCH MAPLE E 19.9'
DUG OUT STONE SET 1 1/4 INCH PIPE (NO DATE)
PK NAIL 28 INCH MAPLE N 35°W 61.10
PK NAIL SE SIDE P.POLE S 30°W 60.65
PK NAIL S SIDE 30 INCH MAPLE E 20.56
C/L GRAVEL ROAD

NO OTHER CORNER HISTORY

