

RE

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
Shirley A. ...

00 FEB -1 AM 8:48

FILED

LIBRARY / PAGES 1 /

SECTION

FOR CORNERS IN:
ALLEGAN COUNTY

1. Public Land Survey

LOCATED IN: T...2N... R...11W

CORNER CODE # E-7
MARVIN TWP.

2. Property Controlling in section

3. Miscellaneous Property in Sec.

4. Lot No....., Recorded Plat.....

5. Private Claims.....

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on May 11, 1999, do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-7

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED *05/11/1999*
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-7

FOUND 1 1/2" PIPE IN MON BOX PER # 5 ABOVE. 4" GAS PIPE CORNER POST EAST 30.8' REMAINS.
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-7

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX.

- IN C/L N-S ROAD
- TOP C/L 4 INCH STEEL FENCE POST EAST 31.40'
- TOP C/L TCB N 15°W 165.57'
- NORTH EDGE STOP / STREET SIGN POST S 85°W 41.86'
- EAST EDGE SPEED LIMIT SIGN POST S 10°W 152.29'
- NAIL AND TAG SOUTH SIDE 12 INCH CHERRY N 85°W 197.18'

Raymond Moored Date *12/13/99*

Surveyors License No. *26463*



PROPERTY &
RECORDS

MAR 07 2000

SECTION

GOVERNMENT CORNER HISTORY
E-7
TOWN 2 NORTH, RANGE 11 WEST,
MARTIN TOWNSHIP, ALLEGAN COUNTY, MICHIGAN

LEINO 007 PAGE 378

1. GLO NOTES

SET POST CORNERS OF SECTIONS 16, 17, 20, & 21
WITNESSES: WHITE OAK 25 N 37 1/2 E 67
DO 6 SE 102

2. COUNTY SURVEYOR NOTES 1878
STAKE & STONE FOR NW CORNER SEC. 21

3. H. McDOUGAL CO. SURVEYOR 1898 NOTES
(SECTION 16) STAKE FOR SW CORNER

4. D.A. RATEKIN CO. SURVEYOR CIRCA 1960'S
SURVEY FOR C. RUSSELL NOTES SECTION CORNER
NO WITNESSES

5. D.A RATEKIN CO. SURVEYOR 1966
SECTION CARD INFORMATION (SECTION 21) NOTES STONE WITH X & BRICK AROUND
PLACED 1 1/2 IRON PIPE ABOVE STONE
WITNESSES: 4 INCH GAS PIPE CORNER POST E 30.8 FEET
STREET SIGN NE 24.1'
TELEPHONE POLE NW 46.0 FEET
TELEPHONE POLE SSW 86.3 FEET
NORTH END 12 INCH CONCRETE CULVERT NW 41.6 FEET
SOUTH END 12 INCH CONCRETE CULVERT SW 37.0 FEET
28 INCH WILD CHERRY WNW 109.46 FEET

6. D.A. RATEKIN CO. SURVEYOR 1974
SECTION CARD INFORMATION (SECTION 20) NOTES 1 1/2 INCH PIPE
WITNESSES: C/L NORTH END 12 INCH CONCRETE CULVERT N 50°W 41.5 FEET
C/L SOUTH END 12 INCH CONCRETE CULVERT S 55°W 37.0 FEET
4 INCH STEEL CORNER FENCE POST EAST 30.9 FEET

7. L.C.R.C. RECORDED BY D.A. RATEKIN 1974
WITNESSES SAME AS ITEM # 5 & ITEM # 6

8. D.A. RATEKIN, CO. SURVEYOR 1980
SURVEY FOR M. DEMANN NOTES CORNER
WITNESSES SAME AS ITEM # 6

9. TRI COUNTY LAND SURVEYING 1985
SURVEY FOR J. SANGSLAND NOTES CORNER
WITNESSES SAME AS ITEM # 5

10. TRI COUNTY LAND SURVEYING 1986
QUARTER SECTION BREAKDOWN
NOTES CORNER NO WITNESSES

11. TRI COUNTY LAND SURVEYING 1986
SURVEY FOR CORNELL & ASSOCIATES 86-084 NOTES CORNER
WITNESSES SAME AS ITEM # 5

12. TRI COUNTY LAND SURVEYING 1986
SURVEY FOR CORNELL & ASSOCIATES 86-155 NOTES CORNER
WITNESS SAME AS ITEM # 5

