

SURVEY & REMONUMENTATION

APR 29 1996

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>2 N</u> R <u>11 W</u>	<u>E-13(SE,32)</u> <u>Martin</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN

1995 APR 24 PM 2:20

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David F. Peabody, in a field survey on November 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | |
|----------------------|---------------------------------|
| G.L.O. (Set Post) | Ratekin LCRC (L.02, P.126) 1973 |
| W. Oak 10 N511/2E 23 | Found Iron |
| Do. 17 N46W 21 | PK Nail in P. Pole S45°E 81.26' |
| | PK Nail in T. Pole N15°E 45.67' |
| | PK Nail in 18" Oak N45°W 99.04' |
| | PK Nail in T. Pole S40°W 36.83' |
- Kirk VanOrder survey 1992
- Fd. 3/4" Iron
- Nail in SE Side P. Pole NE 66.36'
- PK & Washer in NE Side P. Pole SE 81.26'
- PK & Washer in SE Side T. Pole SW 36.86'
- Nail in NE Side 19" B. Oak NW 114.90'


- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 3/4" Solid Iron
- G.L.O. All Gone
- PK Nail in P. Pole S45°E 81.26'
- PK Nail in 18" Oak N45°W 99.04'
- PK Nail in T. Pole S40°W 36.83'
- Nail in SE Side P. Pole NE 66.36'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-8-94
COUNTY REP. David F. Peabody

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Approved 11-08-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Removed 3/4" Iron and Placed 3/4" Remon Iron W/Remon Cap
- Fd. PK Nail in SE Side T. Pole S40°W 36.89'
- Fd. PK Nail in NE Side P. Pole S45°E 81.25'
- 20d Nail W/Allegan Co. Tag NW Side P. Pole N60°E 66.21'
- 20d Nail W/Allegan Co. Tag NE Side 36" Oak N45°W 99.3'
- NE Cor. Sec. 5 (Gun Plain Twp.) E-1 West 146.81'
- SW Cor. House N45°E 124.4'
- C/L Rd. North 1'±



118870005 PAGE 171

Signed by David F. Peabody Date 1/26/95

Surveyor's Michigan License No. 25866