

**SURVEY & REMONUMENTATION**

APR 24 1995

**COMMISSION**

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>ALLEGAN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T-2N R-11W	H-7 S1/4-15
	T _____ R _____	MARTIN TWP.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 1994 AUG 16 AM 11:39  
 FILED  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, BASIL ANDRESS, in a field survey on 26 APR, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
 WEST BETWEEN SECTIONS 15 & 22  
 40.21 SET OR. SEC. POST  
 BEECH 12 N82W 23  
 BEECH 6 S40E 16

OLD NOTES CONT.  
 SCHOOL SW 136.7'  
 DIST. E TO SE SEC COR 40.40

COUNTY SURVEYOR'S OLD NOTES  
 STONE  
 SW COR STORE NE 55'  
 TP SE 67'

L.C.R.C.'S  
 L-1, P-224  
 L-3, P-165

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1" IRON IN MON. BOX  
 VESTIGES OF STUMP NE 62'+/-  
 SW COR OF BUILDING OUTLINE IN GRASS NE 55'+/-  
 PP (NEW) SW 36'


**APPROVED REMONUMENTATION CORNER**  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 4-12-94  
 COUNTY REP. [Signature]

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1" IRON W/ STD. ALLEGAN CO. MON.

16d W/ REMON. TAG NW SDE 20" MAPLE N65E 188.12'  
 16d W/ REMON. TAG E SDE PP N10W 140.68'  
 16d W/ REMON. TAG S SDE 16" PINE S75W 105.83'  
 16d W/ REMON. TAG SE SDE PP S35W 37.09'



Signed by [Signature] Date 24 Jun 94  
 Surveyor's Michigan License No. 30075