

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN
 (County)

Located in:

Corner Code ~~##~~

- | | | |
|------------------------------------|--------------------------|---------------------|
| 1. Public Land Survey | T <u>2N</u> R <u>11W</u> | <u>T-5 (NE, 15)</u> |
| | T ___ R ___ | <u>MARTIN TWP.</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

1993 DEC 30 PM 2:42
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
Basil J. Address

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, BASIL ADDRESS in a field survey on DECEMBER 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.- NORTH BETWEEN SECTIONS 14 & 15, 80.00 CHS. SET POST COR. SECTIONS 10, 11, 14 & 15.

WITNESSES: BEECH 7 S 70 E 14 LKS. (11.22')

BEECH 6 N 32 W 30 LKS. (11.88')

COUNTY SURVEYOR'S OLD NOTES: IRON, MEAS. NORTH 1320' TO 1/8 POST CONT. NORTH 1320' TO 1/4 COR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FD. IRON
 IN C/L NORTH & SOUTH RD.
 IN C/L OF RD TO EAST
 IN LINE WITH OCCUPATION TO WEST

THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP 12-21-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- REPLACED IRON W/ STD. ALLEGAN CO. MON. (3/4" STEEL PIN W/ REMON. CAP)
- NAIL & REMON. WASHER N SDE 18" ASH S 75 E 77.58'
- NAIL & REMON. WASHER W SDE 10" PINE N 20 E 95.90'
- NAIL & REMON. WASHER SW SDE 10" ASH N 30 W 113.07'
- NAIL & REMON. WASHER S SDE 11" MAPLE N 55 E 138.91'
- NAIL & REMON. WASHER W ROOT 28" MAPLE N 15 E 143.70'
- NAIL & REMON. WASHER S SDE 8" ASH WEST 53.58'



Signed by Basil J. Address Date 12-29-93
 Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983