

MAR 16 1994

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
For corners in
ALLEGAN
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 2N R 11W	I-7 (SE, 15)
	T _____ R _____	MARTIN TWP.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1993 DEC 30 PM 2:42
Jasper A. Dutton
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

FILED

Register of Deeds Stamp & File Number

I, BASIL ANDRESS, in a field survey on DECEMBER 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. - NORTH BETWEEN SECTIONS 22 & 23 80 CHS. SET POST CORNERS SECTIONS 14, 15, 22 & 23.
 WITNESSES: W. ASH 28 S 11 W 26 LKS. (17.16')
 SUGAR 18 N 32 W 22 LKS. (14.52')
 11-4-1868 - J. W. HICKS, C.S. MEAS. 40.40 CHS. (2666.40') WEST TO 1/4 COR.
 COUNTY SURVEYOR'S OLD NOTES: MEAS. EAST 2656' TO 1/4 COR.
 MEAS. SOUTH 2653.5' TO 1/4 COR.

(CONTINUED ON BACK OF CERTIFICATE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FD. 1" IRON PER PREVIOUS WITNESSES.
 REPLACED 1" IRON WITH STD. ALLEGAN CO. MON.
 THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP 12-21-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 REPLACED 1" IRON W/ STD. ALLEGAN CO. MON. (3/4" STEEL PIN W/ REMON. CAP)
 NAIL & REMON. WASHER E SDE PP S 15 W 71.09'
 NAIL & REMON. WASHER NW SDE 9" ELM S 50 W 63.37'
 NAIL & REMON. WASHER W SDE 15" TWIN ASH S 20 E 87.08'
 NAIL & REMON. WASHER S SDE PP N 80 E 94.56'
 SE COR CONC FND (ADD. TO MAIN STRUCTURE, HSE #389) N 50 E 242.97'



Signed by Basil J. Andress Date 12-29-93
Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1982

(CONTINUED FROM FRONT OF CERTIFICATE)

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/ OR SUBSEQUENT RESTORATION.

COUNTY SURVEYOR'S OLD NOTES: STONE W/ "X"

WITNESSES: MAPLE 12 NW 66.8'
POPLAR 4 NE 46.8'
CHERRY 4 NW 37.2'

1912 - ALLEGAN CO. RD. COMM. SURVEY MEAS. SOUTH 2653.5' TO 1/4 COR.

STONE - WITNESSES: 12" MAPLE NE 66.8'
4 " POPLAR NE 46.8'
14" ELM SE 82.5'

1965 - D. A. RATEKIN, C.S.

FD. IRON IN CENTER OF WHEEL HUB

WITNESSES: MAPLE NE 65.8'
WALNUT 15" 52.6' NE
C/L RD. SOUTH 5'

MEAS. EAST 2655.18' TO 1/4 COR.

MEAS. WEST 2667.06' TO 1/4 COR.

MEAS. NORTH 2642.55' TO 1/4 COR.

1971 - D. A. RATEKIN, C.S. L.C.R.C. (L-1, P-100)

1977 - W. Q. SMITH, R.L.S. L.C.R.C. (L-3, P-165)

1983 - R. E. MOORED, L.L.S. (WIGHTMAN MOORED)

MEAS. WEST 2667.90'

WITNESSES CHECK W/ D. A. RATEKIN'S WITNESSES (L.C.R.C.)

1993 - WIGHTMAN MOORED MEAS. NORTH 2643.48' TO 1/4 COR.