

REMONUMENTATION

APR 24 1995

COMMISSION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T-2N R-11W	J-11 S1/4-26
	T _____ R _____	MARTIN TWP.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1994 AUG 16 AM 11:39
James A. Address, Jr.
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, BASIL ADDRESS, in a field survey on 26 APR, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
 WEST BETWEEN SECTIONS 26 & 35
 40.02 SET QR. SEC. POST
 B. ASH 14 S 55 E 4
 ELM 6 N 32 W 29

OLD NOTES FROM COUNTY SURVEYORS
 STAKE & STONE 4" OAK NW 25.8'

L.C.R.C. L-2, P-335

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FD. 1" IRON OVER STONE OVER 1 1/2" IRON AS CALLED OUT IN L.C.R.C.
 NAIL E SIDE OAK NOSE 76.34'
 NAIL E SIDE PP N35W 46.04'
 CONC. FENCE COR POST (PIPE IN C/L) N05W 34.22'
 C/L E END 24" CMP N40E 36.05'
 C/L E END 36" CMP S45E 35.91'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 5-10-94
 COUNTY REP. Basil A. Address, Jr.

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED IRON-STONE-IRON W/ STD. ALLEGAN CO. MON.
 16d W/ REMON. TAG SW SDE 6" BOX ELDER S40E 88.77'
 16d W/ REMON. TAG W SDE LG. WILLOW CLUMP S20E 102.78'
 16d W/ REMON. TAG E SDE 32" ASH NORTH 86.58'
 16d W/ REMON. TAG SW SDE PP N40W 46.28'
 C/L TOP CONC POST NORTH 34.17'
 C/L 114TH AVE (GRAVEL) NORTH 4'+/-
 IN LINE W/ OCCUPATION TO NORTH



Signed by *Basil A. Address, Jr.* Date 24 JUN 94
 Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983