

Allegan County Remonumentation
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
 (County)

Located In: Corner Code #
 T 2N R 11W K-1 (NW, 1)
 T R Marrin Twp.
 T R
 T R
 S T R
 S T R
 S T R

1995 DEC 14 PM 2:35
 REGISTERED PROFESSIONAL LAND SURVEYOR
 ALLEGAN COUNTY, MICHIGAN
 REGISTER OF DEEDS STAMP & FILE NUMBER

FILED

SURVEY &
 REMONUMENTATION
 APR 29 1996
 COMMISSION

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. _____, Recorded Plat _____
- Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	31	32	33	34	35	36					
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on July 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- K-1 John Mullett, 1826 LCRC L004, P29
 - Intersected N Boundary 1" iron, 1984
 - 90 lks E post 22" Hickory S 70 E 80.5'
 - Set post cor. 1 & 2 60" Oak N 70 W 60.5'
 - B. Oak 14 S 38 E 49 C/L rd. N 1'±
 - Birch 12 S 55 W 57 PP S 65 W 52.5'


APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 8-14-95
 COUNTY REP. [Signature]

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- K-1 Found 1" iron in Mon. Box
 - PP S 65 W 52.5'

Place cor. on South line Twp. 0.21' North of existing iron
 And is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-1 Set Allegan Co. Mon. 3/4" x 24" Pin with Cap on Twp. line in Mon. box
 - Mon. is on N edge of box
 - Nail & Allegan Co. Remon. Tag in S side PP N 75 E 141.81'
 - Nail & Allegan Co. Remon. Tag in N side PP N 80 W 242.85'
 - Nail & Allegan Co. Remon. Tag in N side PP S 65 W 53.01'
 - NE cor. conc. porch hse. #214 S 70 W 242.23'
 - C/L bit. E-W, North 1'±; no field division South; PK set N & W 1.00'
 - Allegan Co. Mon. SW cor. 36, 3-11 West 59.68'

Signed by John C. Bueche Date Oct 7, 1995
 Surveyor's Michigan License No. 13027



0005 PAGE 247