

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ALLEGAN</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T-2N R -11W	K-11 SE-26
	T _____ R _____	MARTIN TWP.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
James L. Webster

1994 AUG 16 AM 11:39

FILED

Register of Deeds Stamp & File Number

I, BASIL ADDRESS, in a field survey on 26 APR, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
 NORTH BETWEEN SECTIONS 35 & 36
 80.00 SET POST COR. SECTIONS - 25, 26, 35 & 36
 B. ASH 16 S 17 E 32
 ELM 34 N 42 W 13
 OLD COUNTY SURVEYOR'S NOTES
 STAKE
 DISTANCE WEST TO 1/4 COR. 40.25

CONT. ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FD. 1/2" IRON IN MON. BOX
 NE COR I-BEAM BRIDGE WNW 30.83'
 SE COR I-BEAM BRIDGE WSW 30.07'
 PP NE 67.75'
 TEL. PED. (CEN. OF TOP) ENE 97.1'

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" IRON W/ STD. ALLEGAN CO. MON.

16d W/ REMON. TAG NW SDE PP S 75 W 125.79'
 16d W/ REMON. TAG NE SDE 24" MAPLE N 80 W 155.57'
 16d W/ REMON. TAG NW SDE PP N 40 E 67.95'
 16d W/ REMON. TAG SW SDE 24" MAPLE S 45 E 107.23'
 16d W/ REMON. TAG SW SDE PP S 15 E 149.68'
 IN C/L 2ND. ST (BIT)
 C/L 114TH. AVE TO WEST IS NORTH 3'+/-
 C/L 114TH. AVE TO EAST IS NORTH 5'+/-



Signed by *Basil Address* Date 24 JUN 94
 Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

LIBER 0004 PAGE 404

SHEET 1 OF 2

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 5-10-94
 COUNTY REP. *Basil J. Address*

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/ OR SUBSEQUENT RESTORATION.

OLD COUNTY SURVEYOR'S NOTES

IRON

ELM 4 SW 51.2'

ASH 6 SE 76'

DIST. E TO 1/8 POST 1327'

DIST B'TW'N N1/4 - NE (SEC-36), 2654'

DIST. S TO 1/8 POST 1327.5'

DIST. S FOR MILE 5310'

DONALD A. RATEKIN, C.S.

1964

1/2" IRON OVER WHEEL HUB

NE COR I-BEAM BRIDGE WNW 30.83'

SE COR I-BEAM BRIDGE WSW 30.07'

PP NE 67.75'

TEL. PED. (CEN. TOP) ENE 97.1'