

Allegan County Remonumentation
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan
 (County)

Located in:

Corner Code #

1. Public Land Survey	T <u>2N</u> R <u>11W</u>	<u>M-2 (E.L. 1)</u>
	T ___ R ___	<u>Martin Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

1995 DEC 14 PM 2:35
 J. C. Bueche
 ALLEGAN COUNTY REGISTER OF DEEDS

FILED

**SURVEY &
 REMONUMENTATION**

**APR 29 1996
 COMMISSION**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on July 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2 GLO Jan. 11, 1826	LCRC L4, P184, Jan., 1993
John Mullett, D.S.	1/2" rerod w/Jonker cap
Set post	Spk. in NE side 10" Mulberry N 65° W 39.49'
Tam 6 S 14 W 61	Spk. in NW side 14" Poplar N 60° E 32.20'
Do 6 N 38 W 64	Spk. in S side 18" Poplar N 40° E 44.55'
	PK nail in SW side PP S 55° E 63.19'
	Falls on C/L 20'± N-S gravel rd.
	Falls on C/L 4' flat bottom ditch to the West (which bears S 88° W)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 Found capped rerod as per wit.

And is accepted as a careful and faithful perpetuation of the position of the original corner.


APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 9-14-95
 COUNTY REP. Paul L. Van Dusen

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Replaced rerod with Allegan Co. Mon. (3/4" x 24" rod w/cap)
 PK in SW side PP S 55° E 63.19'
 Nail & Allegan Co. Remon. Tag in NW side 16" Poplar N 60° E 31.24'
 Nail & Allegan Co. Remon. Tag in NW side 16" Poplar N 45° E 47.84'
 Nail & Allegan Co. Remon. Tag in N side 10" Willow S 50° W 79.14'
 On C/L gravel N-S, on C/L ditch West
 Barry Co. Mon. W 1/4 Sec. 6, 2-10 South 49.92'

Signed by John C. Bueche
 Surveyor's Michigan License No. 13027

Date Oct 2, 1995



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

USE 0005 PAGE 249