

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>11W</u>	<u>M-3 (SE, 1)</u>
	T _____ R _____	<u>Martin Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1995 DEC 14 PM 2:35
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 FILED

Register of Deeds Stamp & File Number

**SURVEY &
REMONUMENTATION
APR 29 1996
COMMISSION**

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on July 12, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

M-3 GLO, Jan., 1826	LCRC L3, P149
John Mullett, D.S.	1 1/2" iron, May, 1977
Set post	PP N 45 E 51.65'
B. Ash 16 S 50 1/2 W 31	P&G pole S 60 E 78.00'
Tarm 8 N 36 W 37	PP N 60 W 122.67'
	C/L rd. 7' West
	SW cor. Sec. 6, 2-10, South 49.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 Found rerod	PP N 45 E 51.65'
	PP N 60 W 122.67'
	SW cor. Sec. 6, 2-10, South 49.5'


And is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 9-14-95
 COUNTY REP. John C. Bueche

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 Replaced rerod w/Allegan Co. (3/4" x 24" Pin w/Cap)
 Face of cor. fence post N 45 W 50.23'
 Face of cor. fence post N 20 W 100.10'
 Existing Nail & Tag in N side PP N 50 E 51.63'
 Conc. Nail & Allegan Co. Remon. Tag in S side PP N 70 W 124.32'
 Existing Nail & Tag in NE side PP S 35 E 94.32'
 On C/L gravel rd. West
 C/L gravel rd. N-S, West 9'±
 T iron SW cor., Sec. 6, 2-10, South 49.48'

Signed by John C. Bueche Date Oct 2, 1995
 Surveyor's Michigan License No. 13027



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 21, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983