

MAR 07 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY MI 49700

00 FEB - 1 AM 8:48

FILED
11880007 11/13/99

| | | |
|---------------------------------------|-------------------------|---------------|
| FOR CORNERS IN: ALLEGAN COUNTY | LOCATED IN: | CORNER CODE # |
| 1. Public Land Survey | T. 2N R. 11W | M-4 |
| EAST 1/4 POST, SEC. 12 MARTIN TWP. | T. R. | |
| | T. R. | |
| | T. R. | |
| 2. Property Controlling in section | S. T. R. | |
| | S. T. R. | |
| 3. Miscellaneous Property in Sec. | S. T. R. | |
| 4. Lot No., Recorded Plat. | | |
| 5. Private Claims. | | |

REGISTER OF DEEDS STAMP & FILE NUMBER

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 6 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Raymond Moored in a field survey on Sept. 7, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 40.00 CH. SET QR. SEC. POST IN MARSH, NO BEARINGS

D. RATEKIN WITNESS CARD
IRON PIPE (CO. ROAD COMM.)

NO OTHER CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED OCT. 12, 1999.
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 2" X 36" LONG ANGLE IRON 2642.31' S OF NE COR OF SEC. (M-3)
FD NO OTHER EVIDENCE OF POSITION OF CORNER.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.
REMOVED ANGLE IRON AND SET STANDARD ALLEGAN CO. REMON IRON W/CAP.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON OCT. 12, 1999.

TOTAL TRAVERSING= 2642.31' ON ROAD

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON W/ CAP

- SE COR METAL BLDG N 45 W 42.70'
- NE COR METAL BLDG N 25 W 93.60'
- TOP WEST END 36" C.M.P. S 50 W 39.90'
- EAST & WEST DITCH 21' SOUTH
- NAIL IN S. SIDE OF P. POLE S 85 E 31.52'
- A-4, T2N, R10W SOUTH 39.37'

Raymond Moored Date 11/10/99

Surveyors License No. 26463

