

MAR 6 7 2000

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS  
ALLEGAN COUNTY, MICHIGAN  
*Janice A. Carter*

00 FEB - 1 AM 8:48

LIBRARY / FILED  
70000001 / FILED 02

SECTION

|   |                               |               |
|---|-------------------------------|---------------|
| FOR CORNERS IN:<br>ALLEGAN COUNTY           | LOCATED IN:                   | CORNER CODE # |
| 1. Public Land Survey                       | T. <u>2</u> N. R. <u>11</u> W | .....M-6.     |
| EAST 1/4 CORNER,<br>SEC. 13, MARTIN<br>TWP. | T..... R.....                 | .....         |
|   | T..... R.....                 | .....         |
|   | T..... R.....                 | .....         |
| 2. Property Controlling<br>in section       | S.....T.....R.....            | .....         |
|   | S.....T.....R.....            | .....         |
| 3. Miscellaneous<br>Property in Sec.        | S.....T.....R.....            | .....         |
| 4. Lot No.....Recorded Plat.....            |                               |               |
| 5. Private Claims.....                      |                               |               |

REGISTER OF DEEDS STAMP & FILE NUMBER

I, Raymond Moored in a field survey on AUG. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  | 8  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO, CIRCA 1830; NOTES:  
40.00 CH'S SET TO QR. SEC. POST  
WITNESSES: RED OAK 18 S 5 1/2 W 447  
RED OAK 10 S 59 W 203
- HUGH MAC DOUGALL, CO. SURVEYOR; 5-17-1926  
FD. E 1/4 CORNER  
WELL POINT  
OAK 4" SE 39.8'  
OAK 8" NE 31.5'  
MAPLE NE 46'  
18.5' JOG SOUTH TO W 1/4 POST SECTION 18, T2N, R10W,  
(ALSO NOTED AS WELL POINT)

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED OCT. 12, 1999  
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1 1/2" WELL POINT 1.5'+/- DEEP WITH 2 1/2" PIPE ALONG SIDE  
26" OAK SE MEASURES 38.4' MAYBE SAME WITNESS TREE.  
COULD NOT FIND WELL POINT FOR A-6, T.2N., R.10W.  
  
SET 3/4 X 24" ALLEGAN COUNTY REMON IRON WITH CAP INSIDE OF WELL POINT  
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
  
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON OCT. 12, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" x 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP INSIDE OF 1 1/2" WELL POINT.  
  
-NAIL & TAG IN E SIDE 20" OAK S14E 36.73'  
-NAIL & TAG IN W SIDE POWER POLE S05E 45.94'  
-NAIL & TAG IN W SIDE POWER POLE S20W 16.40'  
-NAIL & TAG IN W SIDE FENCE POST S21W 45.89'

*Raymond Moored*  
Date 12/14/99

Surveyors License No. 26463

