

MAR 07 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY MICH.
James A. ...

00 FEB -1 AM 8:48

FILED

FOR CORNERS IN:
ALLEGAN COUNTY

1. Public Land Survey
SE CORNER SEC. 13
NE CORNER SEC. 24
MARTIN TOWNSHIP

LOCATED IN:

T.....2N R.....11W
T..... R.....
T..... R.....
T..... R.....

CORNER CODE #
...M-7.....
.....
.....
.....

2. Property Controlling
in section

S.....T.....R.....
S.....T.....R.....

3. Miscellaneous
Property in Sec.

S.....T.....R.....

4. Lot No.....Recorded Plat.....

5. Private Claims.....

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	28	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Aug. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED OCT. 12, 1999
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1-1/2" PIPE IN MON BOX PER WITNESSES IN NO. 4 AND 10 ON BACK OF SHEET.
REMOVED PIPE AND SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP IN MON BOX
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY THE ALLEGAN COUNTY REMON PEER GROUP ON OCT. 12, 1999
TOTAL OFF ROAD TRAVERSING: 2652.33'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX.
-FD NAIL IN 6" WILD CHERRY S55W 41.60'
-FD NAIL IN N. SIDE P. POLE S53E 61.95'
-FD NAIL IN FACE 24" B. WALNUT N03E 31.75'
-FD NAIL IN NE SIDE 30" OAK N55W 51.75'
-C/L PAVEMENT (118TH AVE) SOUTH 1.0'
-C/L ROAD TO SOUTH (BOYSEN RD.) EAST 2'+/-
-A-7 T.2N., R. 10W. SOUTH 11.88'

Raymond Moored
Date 11/10/99
Surveyors License No. 26463



MAR 07 2000

SECTION

GOVERNMENT CORNER HISTORY
SOUTHEAST CORNER OF SECTION 13,
TOWN 2 NORTH, RANGE 11 WEST
M-7

LIBERO 007 PAGE 3 84

1. GLO CIRCA 1830, 80.00 CH'S.
SET POST COR SEC'S 13 & 24
WITNESSES: W. OAK 7 N37W 43
 W. OAK 7 S 23 1/2 W 28
 2. HUGH MAC DOUGALL, COUNTY SURVEYOR
W. OAK 20°SE 36.4'
W. OAK 24 NW 3
ELM 16 SW 79'
 3. HUGH MAC DOUGALL, COUNTY SURVEYOR 5-17-1926
WITNESS ; SAME AS ABOVE
 4. D.A. RATEKIN, CO. SURVEYOR
SECTION 13 CARD INFORMATION
SE CORNER SET STONE & PIPE (CO ROAD COMM.)
WITNESSES: W. OAK 36" SE 36.11'
 W. OAK 36" NW 94.9'
 ELM 16" SW 79.18'
- SECTION 24 CARD INFORMATION
1922 ROAD SURVEY
NE COR IRON PIPE & STONES
SW 95.9 FEET CORNER of HOUSE
SW 78.6 28 INCH ELM
SE 96.7 FEET 12 OAK
36 INCH OAK SE 36.4 FEET
36 INCH OAK NW 94. FEET
16 INCH ELM SW 79.1 FEET
- 1974 WITNESSES
1/2 INCH IRON
HACK IN 18 INCH WALNUT N 31.88 FEET
P.K. NAIL & HACK IN 18 INCH OAK N 60°W 51.05
P.K. NAIL & WASHER IN P. POLE S 60°W 61.7
4 INCH CHERRY (FACE) S 40°W 41.75
5. D.A. RATEKIN, CO. SURVEYOR; 10-7-1974
SURVEY FOR E. SNYDER NOTES CORNER, WITNESSES SAME AS ITEM #4
 6. L.C.R.C. by D.A. RATEKIN, CO. SURVEYOR, 4-24-1975
NOTES WITNESS SAME AS ITEM #4 AND ITEM #5 (LIBER 2, PAGE 418)
 7. L.C.R.C. by D. F. PEABODY, SURVEYOR, 7-22-80
NOTES FOUND STONE
FENCE E & W SOUTH 1'
FENCE POST S 85°E 6.3'
FENCE POST S 85°W 10.7'
DOESN'T APPEAR TO BE THIS CORNER
 8. WIGHTMAN-MOORED, INC. SECTION BREAKDOWN 5-13-1992
FOUND MON BOX
 9. WIGHTMAN-MOORED, INC. SURVEY 5-15-92
SURVEY FOR J. FENTON
NOTES CORNER, NO WITNESSES
 10. WIGHTMAN-MOORED, INC. SURVEY 5-16-96
NOTES CORNER AND WITNESSES
1 1/2 INCH IRON
PK NAIL 36 INCH OAK N 55°W 52.50'
PK NAIL P. POLE N 07°W 43.68'
PK NAIL P. POLE S 55°E 61.94'
IN C/L E&W ROAD
 11. HOLLAND ENGINEERING
SECTION CARD INFORMATION
SAME AS # 7.