

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

James W. Moore
REGISTER OF DEEDS
ALLEGAN COUNTY, MI

00 FEB - 1 AM 8:48

FILED

1100007 PAGE 3 OF 5

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T. <u>2N</u> R. <u>11W</u>	<u>M-8</u>
EAST 1/4 POST SEC. 24, T2N, R11W.	T. R.	<u>MARTIN TWP.</u>
	T. R.
	T. R.
2. Property Controlling in section	S. T. R.
	S. T. R.
3. Miscellaneous Property in Sec.	S. T. R.
4. Lot No., Recorded Plat.		
5. Private Claims.		

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on AUG. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO NOTES;
SET QR POST 40.00 CH'S
WITNESSES: W. OAK 7 N 37 W 43
W. OAK 7 S 23 1/2 W 28
- WIGHTMAN MOORED, INC. 5-13-92 NOTES:
SECTION BREAKDOWN
FD 1/2" IRON
- WIGHTMAN MOORED, INC. 5-16-96 NOTES:
BOUNDARY SURVEY FD 1/2" IRON
1/2" IRON S 17.56'
NAIL IN 32" OAK S 43 W 20.63'
PK IN P. POLE N 79.45'
IN C/L of ROAD

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED OCT. 12, 1999.
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1/2" IRON ROD PER #3 ABOVE. ALL WITNESSES REMIAN.

SET 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND ROD.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON OCT. 12, 1999.

TOTAL ON ROAD TRAVERSING= 2640.44'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
 FD NAIL IN P. POLE N 48 E 79.45'
 NAIL & TAG IN E'LY SIDE of 18' MAPLE S 38 W 130.50'
 NAIL & TAG IN E'LY SIDE of 20" OAK N 10 W 91.73'
 NAIL & TAG IN W'LY SIDE of 4" OAK S 25 E 58.10'
 C/L of ROAD WEST 1.5'
 A-8, T2N, R10W S 17.59'

Raymond Moored

Date 11/10/99

Surveyors License No. 26463

