

MAR 6 7 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY
Spencer A. ...

00 FEB - 1 AM 8:48

FILED

RECORDED / FILED

FOR CORNERS IN: ALLEGAN COUNTY

LOCATED IN: T. 2N R. 11W

CORNER CODE # M-9

1. Public Land Survey
SE CORNER of SEC. 24
NE CORNER of SEC. 25
T2N, R11W.
T. R.
T. R.
T. R.

MARTIN TWP.

2. Property Controlling in section
S. T. R.
S. T. R.

3. Miscellaneous Property in Sec.
S. T. R.

4. Lot No., Recorded Plat.

5. Private Claims.

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Raymond Moored in a field survey on AUG. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED OCT. 12, 1999
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1" IRON IN 1 1/2" PIPE PER RATEKIN L.C.R.C.
REMOVED AND SET 3/4" X 24" ALLEGAN CO. REMON IRON WITH CAP.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON OCT. 12, 1999.

TOTAL ON ROAD TRAVERSING= 2646.75'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

NAIL & TAG IN NE SIDE of 8" MAPLE CLUMP	N 52 W	45.40'
NAIL & TAG IN E SIDE of 16"/ 14" TWIN ASH	N 11 E	68.85'
NAIL & TAG IN NE SIDE of 14" ASH	S 42 E	48.58'
NAIL & TAG IN W SIDE BASSWOOD CLUMP	S 85 E	17.80'
A-9, T2N, R10W	SOUTH	16.50'
IN CENTERLINE of ROADS	N, S, & W	

Raymond Moored Date 11/10/99

Surveyors License No. 26463



MAR 07 2008

SECTION

LIBERO 007 PAGE 87

GOVERNMENT CORNER HISTORY FOR
M-9
TOWN 2 NORTH, RANGE 11 WEST,
MARTIN TOWNSHIP, ALLEGAN COUNTY, MICHIGAN

1. GLO NOTES:

80.00 SET POST COR. SECT'S 24 & 25
WITNESSES: B. OAK 7 S 53 W 20
DO 15 W 40

2. H. Mac DOUGALL; CO. SURVEYOR 5/15/1918 NOTES:

DEAL INTERCOUREY DRAIN " THENCE EAST 161.41 RODS, TERMINATING 25 FEET
NORTH OF THE SOUTHEAST CORNER OF SECTION 24, TOWNSHIP 2 NORTH, RANGE
11 WEST."

3.D.A. RATEKIN; CO. SURVEYOR NOTES:

SECTION CARD INFORMATION E ¼ POST SET '74 1 ½" IRON
C/L E END of CMP S 45° W 31.17
C/L W END of CMP S 55° E 33.25'
IRON S (JOG COR) 19.5'

4.D.A. RATEKIN; CO. SURVEYOR NOTES:

L.C.R.C. RECORDED IN LIBER 2 PAGE 285 ON 6/11/1974
FD 1 ½ IRON PIPE

WITNESSES: 16" TWIN BURR OAK S 50° W (NAIL IN E. SIDE) 64.60'
ST. SIGN EAST 10.05'
12" BURR OAK S 25° E (NAIL IN W. SIDE) 41.87'
18" BURR OAK N 75° E (NAIL IN N. SIDE) 47.77'

5. WIGHTMAN MOORED, INC. 5/13/1992 NOTES:

SECTION BREAKDOWN NOTES CORNER; NO WITNESSES.

