

MAR 6 7 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

Joyce L. ...
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

00 FEB - 1 AM 8:48

LIBRARY / MAR 3 1999
FILED

FOR CORNERS IN: ALLEGAN COUNTY

LOCATED IN: CORNER CODE #

1. Public Land Survey T.2N... R..11W M-10
EAST 1/4 POST SECTION 25
MARTIN TOWNSHIP T..... R.....
T..... R.....
T..... R.....

2. Property Controlling in section S.....T.....R.....
S.....T.....R.....

3. Miscellaneous Property in Sec. S.....T.....R.....

4. Lot No....., Recorded Plat.....

5. Private Claims.....

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on AUG. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. G.L.O. NOTES
HUGH Mac DOUGALL CO. SURVEYOR; 1900'S
DESCRIPTION of RENO DRAIN NOTING CORNER
- 2. D.A. RATEKIN, CO. SURVEYOR: 1974
SET 1 1/2" IRON
C/L S. END 24" CMP S45W 31.17'
C/L W. END 24" CMP S55E 33.25'
ORANGEVILLE COR. (A-10, T.2N., R.10W.) S 19.5'

NORTH E. SIDE SEC. 25 40.00
SET GR SEC POST IN MARSH, NO
BEARINGS. TOO WET TO RAISE A
MOUND.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED OCT. 12, 1999
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1 1/2" IRON ROD PER #2 LISTED ABOVE.
REMOVED AND SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMON IRON W/CAP IN PLACE OF FD. COR.
ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.
APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON OCT. 12, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
- W. END 30" CMP S45W 31.18'
- E. END 30" CMP S45E 33.25'
- 3.0' WEST OF C/L ROAD
- A-10, T.2N., R.10W. SOUTH 19.58'

Raymond Moored
Date 11/10/99
Surveyors License No. 26463

