

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

REGISTER OF DEEDS
ALLEGAN COUNTY, MI
Joyce A. ...

00 FEB - 1 AM 8:48

FILED

100000 / PAGE 389

FOR CORNERS IN: ALLEGAN COUNTY

1. Public Land Survey
SOUTHEAST CORNER OF SECTION 25, T2N, R11W,
NORTHEAST CORNER SECTION 36, T2N, R11W.

2. Property Controlling in section

3. Miscellaneous Property in Sec.

4. Lot No., Recorded Plat.

5. Private Claims.

LOCATED IN: T.2N R.11W

CORNER CODE # M-11
MARTIN TWP

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on AUG. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED OCT. 12, 1999
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 3/4" IRON PER ITEMS NUMBER 2 & 3 LISTED ON BACK OF SHEET.
3 POWER POLE WITNESSES CHECKED OK

SET 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND CORNER.
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON OCT. 12, 1999.

TOTAL ON ROAD TRAVERSING= 2642.22'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
- NAIL IN P. POLE N45E 71.60'
- FD. NAIL IN P. POLE (S. SIDE) N70W 113.55'
- NAIL IN P. POLE S25E 65.10'
- W. END 16" CMP N30W 32.50'
- E. END 16" CMP N25E 30.20'
- A-11, T.2N., R.10W. SOUTH 22.44'

Raymond Moored
Date 11/10/99

Surveyors License No. 26463



ST. LOUIS, MO
RECORDS

MAR 07 2000

SECTION

M-11

SOUTHEAST CORNER SECTION 25
NORTHEAST CORNER SECTION 36
TOWN 2 NORTH, RANGE 11 WEST
MARTIN TOWNSHIP

A. Description of original monument and accessories and/or subsequent restoration:

1. GLO
CIRCA 1830
80.00 Ch., Set post cor Sec's 25 + 36
Elm 8 S 1832
And a Elm 8 S87W 1085
2. DA Ratekin, County Surveyor Notes, Circa 1966
Set 3/4" Iron
Nail in S. side P. Pole N70W 113.55'
1/2" Iron South 33'
Well SSW 33.4'
St. Sign NE 20.4'
P. Pole NE 71.6'
4. Tri County Surveys, Boundary Survey Dated 1988
Fd. 3/4" Iron w/cap
-Fd. nail in S side P. Pole WNW 113.55'
-PK nail in W side P. Pole SE 64.97'
-PK nail in S. side P. Pole ENE 70.55'
-C/L 114TH Ave. S 3'+/-
-C/L Boysen Road W 4'+/-
-In line with occupation to South
No other corner history available.



LIBERO 007 MAR 3 9 0