

RF

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY
Joyce L. Bennett

00 FEB - 1 AM 8:48

FILED

INPROUD 7 PAGE 3 91

FOR CORNERS IN:
ALLEGAN COUNTY

SECTION LOCATED IN: CORNER CODE #

1. Public Land Survey T.2N... R.11W... M-12

EAST 1/4 POST
SECTION 36
MARTIN TWP.
T..... R.....
T..... R.....
T..... R.....

2. Property Controlling
in section S..... T..... R.....
S..... T..... R.....

3. Miscellaneous
Property in Sec. S..... T..... R.....

4. Lot No....., Recorded Plat.....

5. Private Claims.....

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on AUG. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED OCT. 12, 1999
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" SOLID IRON PER ITEMS NUMBER 2 & 3 LISTED ON BACK OF SHEET.

SET 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND CORNER.
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON OCT. 12, 1999.

TOTAL OFF ROAD TRAVERSING= 2644.52'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
- NAIL IN 6"X6" FENCE POST S17E 9.85'
- NAIL IN R.R. TIE FENCE POST S80E 39.60'
- NAIL IN 16" HICKORY N54W 38.35'
- NAIL IN 10" HICKORY N23E 15.10'
- IN S'LY EDGE OF LANE AND IN LINE W/OCCUPATION LINE TO SOUTH

Raymond Moored
Date 11/10/99

Surveyors Liscense No. 26463



REF

MAR 07 2000

SECTION

LIBERO 007 PAGE 392

M-12

**EAST ¼ POST SECTION 36
TOWN 2 NORTH, RANGE 11 WEST
MARTIN TOWNSHIP**

A. Description of original monument and accessories and/or subsequent restoration:

1. GLO
CIRCA 1830
40.00 Ch., Set QR Sec. Post
W. Oak 12 N40W 9
B. Oak 12 S40W 74

2. DA Ratekin, section card
1" iron
10" Hickory South 40.00'
Fence Corner East 28.25'
Fence Corner South 17.7'
Fence Corner S30E 17.4'

3. DA Ratekin, LCRC Liber 2, Page 418, Rec. 4-24-75
Same as #2 Above

4. D. Peabody Survey 5-4-88
Used Corner, No witnesses

No other corner History Available

