

SURVEY & REMONUMENTATION

MAY 05 1997

COMMISSION

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located in:	Corner Code
ALLEGAN (County)		
1. Public Land Survey	T IN R 11W	* M-1 (NE, 1) GUN PLAIN TWP
	T R	
	T R	
	T 2N R 11W	* M-13 (SE, 36) MARTIN TWP
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

1995 DEC 14 PM 2:33
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													

I, BASTL ADDRESS in a field survey on 14 OCT 19 95 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessions and/or subsequent restoration:
G.L.O.
SET TWP COR 40 LKS S OF TEMP. POST
W. OAK 9 44 1/2° W 29
E. OAK 12 S 65° E 17.

CONF. ON BACK
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FD 2" TILE W/ ROCKS AROUND IT.
TWIN OAK W 41.0'±
16" OAK S 10° E 9.5'±
DIST S TO M-2 2673.75'
DIST W TO L-1 2641.01'
SET STD. ALLEGAN CO. MON. IN CENTER OF TILE
AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL MONUMENT.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 9-12-95
COUNTY REY [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
STD. ALLEGAN CO. MON. (3/4" X 24" IRON W/ CAP) IN 2" TILE W/ STONES AROUND IT.
16d REMON TAG W. SDE 16" OAK S 10° E 9.53'
16d REMON TAG NE. SDE 12" OAK S 55° E 25.29'
16d REMON TAG-S SDE 14" OAK N 85° E 27.70'
16d REMON TAG W SDE 22" MAPLE N 15° E 47.44'
16d REMON TAG N SDE 10" MAPLE N 75° W 41.92'
16d REMON TAG NW SDE 6" MAPLE S 60° W 30.54'
IN LINE W/ OLD DOWN FE TO EAST



Signed by [Signature] Date 4 Dec 95
Surveyor's Michigan License No. 30075

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION

A. DESCRIPTION OF . . . SUBSEQUENT RESTORATION

CRESSY, HARRY CO. SURVEYOR 1884
FD OLD BEARINGS & POST SET TILE
W. OAK 12 N 41 1/2° W 19 1/2'
W. OAK 14 N 22° E 17'

OLD ALLEGAN COUNTY SURVEYORS' NOTES
2" TILE W/ ROCKS AROUND IT.
TWIN OAK W 41.0'
12" SOFT MAPLE NW 16.2'

D.A. RATEKIN, C.S. 1971
DIST S TO M-2 2623.82
DIST W TO L-1 2642.29

L.C.R.C. L-1, P- 193 4-18-72
2" TILE W/ ROCKS AROUND IT
30" MAPLE N 50° W 15.6'
40" TWIN OAK W 41.0'
20" MAPLE S 15° E 9.4'

