

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

| <u>ALLEGAN</u> <small>(County)</small> | Located In: | Corner Code ## |
|---|----------------------------|------------------------------------|
| 1. Public Land Survey | T <u>-2N</u> R <u>-12W</u> | D-13 S1/4 -32 <u>WATSON TWP</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

1994 APR 28 AM 9:46
 REGISTERED
 ALLEGAN COUNTY
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 15 | 14 | 13 | 12 | 11 | 10 | 9 | 8 | 7 | 6 | 5 | 4 | 3 |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 30 | 29 | 28 | 27 | 26 | 25 | 24 | 23 | 22 | 21 | 20 | 19 |
| 13 | | | | | | | | | | | | | |

I, BASIL ADDRESS, in a field survey on FEBRUARY 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. LUCIUS LYON, DS
 WEST SOUTH SIDE SEC-32, T-2N, R-12W 40.00 SET QR. SEC. POST
 SUGAR 9 FOR COR. POST
 12-26-78 MID-MICH. ENG. & SURVEY CO. FD. PLOW POINT
 WITNESSES: 27.8' N 10 E 12" TWIN OAKS
 78.35' S 65 E 30" OAK
 96.2' N 60 E 24" OAK
 73.83' WEST N 1/4 COR. SEC-5, OTSEGO TWP.
 2-20-84 TRI-COUNTY LAND SURVEYS, PC USED CORNER FOR SURVEY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
 DATE APPROVED 3-9-94
 COUNTY REP. [Signature]


- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FD. PLOW POINT

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP 3-9-94.

1994 APR 28
 REGISTERED
 ALLEGAN COUNTY
 COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 REPLACED PLOW POINT W/ STD. ALLEGAN CO. MON. (3/4" x 36" STEEL PIN & CAP)
 NAIL & REMON. WASHER E SDE 6" OAK S 15 E 42.22'
 NAIL & REMON. WASHER NW SDE 10" MAPLE S 25 W 41.32'
 NAIL & REMON. WASHER E SDE 12" SHAG BARK HICKORY N 05 E 53.30'
 NAIL & REMON. WASHER SW SDE 6" SHAG BARK HICKORY N 25 W 55.21'
 STD. ALLEGAN CO. MON. (N1/4 COR SEC-5, OTSEGO TWP) WEST 73.87'
 IN LINE W/ OCC TO NORTH
 C/L 112TH AVE (GRAVEL) SOUTH 3' +/-



Signed by [Signature] Date 4-11-94
 Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983