

MAR 16 1994

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
For Corners in
ALLEGAN
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>12W</u>	E-7 (SW,16)
	T _____ R _____	WATSON TWP.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1994 JAN -5 PM 4: 02
Jasper A. Edrington
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, BASIL ADDRESS, in a field survey on DECEMBER 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	8	7	6	5	4	3	2	1					
7													
8	9	8	7	6	5	4	3	2	1				
9													
10	10	9	8	7	6	5	4	3	2	1			
11													
12	11	10	9	8	7	6	5	4	3	2	1		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. - NORTH BETWEEN SECTIONS 20 & 21, 80 CHS. (5280') SET POST COR. SECTIONS-16,17,20 & 21
WITNESSES: SUGAR 13 N 84 W 22LKS. (14.52')
SUGAR 15 N 45 E 40LKS. (26.40')
- COUNTY SURVEYOR'S OLD NOTES: IRON WITNESS-PP NW 116.2'
MEAS. NORTH-2625.36' TO 1/4 COR.
MEAS WEST-2659.2' TO 1/4 COR.
MEAS SOUTH-2654.0' TO 1/4 COR.

(CONTINUED OF BACK OF CERTIFICATE)


- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FD. 1" IRON IN MON. BOX. AS CALLED OUT IN 1991 WIGHTMAN MOORED SURVEY.

PULLED 1" IRON AND SET STD. ALLEGAN CO. MON. IN MON. BOX.

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP 12-21-93.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
REPLACED 1" IRON W/ STD. ALLEGAN CO. MON. (3/4" STEEL PIN W/ REMON. CAP) IN MON. BOX
NAIL & REMON. WASHER SE SDE PP SW 60.47'
NAIL & REMON. WASHER SW SDE 9" JUNIPER SE 96.11'
NAIL & REMON. WASHER NE SDE 12" MAPLE ESE 142.87'
NAIL & REMON. WASHER IN TOP OF R.R. TIE CORNER FENCE POST NW 49.50'



Signed by Basil Address Date 12-31-93
Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

(CONTINUED FROM FRONT OF CERTIFICATE)

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/ OR SUBSEQUENT RESTORATION.

1971-D. A. RATEKIN, C.S.

FD. 1/2" IRON

WITNESSES: ST. SIGN S 45 W 48.3'
 PP S 40 W 61.8'
 PP N 30 W 116.3'

MEAS: EAST 2664.92' TO 1/4 COR.
 SOUTH 2652.51' TO 1/4 COR.

1972-D. A. RATEKIN, C.S.

L.C.R.C. (L-1, P-23)

1976-D. A. RATEKIN, C.S.

L.C.R.C. (L-3, P-39)

1983-D. A. RATEKIN, C.S.

SET 1" IRON AFTER ROAD RECONSTRUCTION

MEAS: NORTH 2624.76' TO 1/4 COR.
 WEST 2660.46' TO 1/4 COR.

1991-R. E. MOORED, R.L.S. (WIGHTMAN MOORED)

FD. 1" IRON IN MON. BOX

MEAS: NORTH 2624.96' TO 1/4 COR.
 EAST 1332.78' TO 1/8 POST CONT. EAST 1332.78 TO 1/4 COR.