

07 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION-
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

Raymond E. Moored
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

00 FEB - 1 AM 8:52

FILED

UNRECORDED

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T.2N..... R.12W.....	E-10
W 1/4 COR., SEC. 28	T..... R.....
E 1/4 COR., SEC. 29	T..... R.....
T.2N., R.12W.	T..... R.....
WATSON TWP.	T..... R.....
2. Property Controlling in section	S.....T.....R.....
	S.....T.....R.....
3. Miscellaneous Property in Sec.	S.....T.....R.....
4. Lot No.....Recorded Plat.....		
5. Private Claims.....		

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	-	-5	-	4	-	-3	-	2	-	-1	-	-
3													
4	7	-	-8	-	9	-	-10	-	11	-	-12	-	-
5													
6	18	-	-17	-	16	-	-15	-	14	-	-13	-	-
7													
8	19	-	-20	-	21	-	-22	-	23	-	-24	-	-
9													
10	30	-	-29	-	28	-	-27	-	26	-	-25	-	-
11													
12	31	-	-32	-	33	-	-34	-	35	-	-36	-	-
13													

I, Raymond Moored in a field survey on Dec 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GLO
NORTH BTWN SECS 28 & 29
40.00 SET QR SEC POST
-BEECH 13 S36E 12
-BEECH 18 N13W 18
- 2. MICH. LAKESHORE RR MAP
-SHOWS E-10 9.00' N OF C/L RR
- 3. 1873 ATLAS
ONLY 1/8th LINE SHOWN IS E-W 1/8th LINE
IN SE 1/4 OF SEC 29, T.2N., R.12W.
- 4. WIGHTMAN MOORED, INC. JAN. 1995
BOUNDARY SURVEY, NE 1/4 SEC. 29
DIDN'T SET E-10, BUT ESTABLISHED
POSITION MID-WAY & ON LINE BTWN E-9 & E-11
- 5. B.J. ANDRESS, P.S., JUNE 1995
BOUNDARY SURVEY NW 1/4 SEC-28
-ESTABLISHED C/L RR BY SPLITTING R/W FES
-ESTABLISHED POSITION OF E-10 9' N OF C/L
RR & ON LINE BTWN E-9 & E-11
-DIST BTWN E-10 & E-9 = 2664.80'
-DIST BTWN E-10 & E-11 = 2655.54'
-E-11 NORTH TO E-W 1/8th LINE OCC = 1328.0'
1/2" IRON W/CAP (#30075)
-C/L OLD RR GRADE SOUTH 9.0'
-16d E. SIDE TW 10" & 13" HICKORY S25°E 25.84'
-16d SE SIDE 10" POPLAR S55°W 32.20'
-16d S SIDE 8" MAPLE N70°W 6.10'
-16d W SIDE 14" ASH N10°E 5.80'
-1/2" IRON W/CAP (#30075) IN OLD FE TO N-E-W N 32.00'
-IN LINE W/ OCC. TO N & S

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/2" IRON W/CAP (#30075) LISTED IN NO. 5 ABOVE GONE DUE TO EXCAVATION. RESET STD. ALLEGAN COUNTY REMON IRON WITH CAP PER REMAINING WITNESSES (#5 ABOVE).

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMON PEER GROUP ON MARCH 9, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 36" ALLEGAN COUNTY REMON IRON AND CAP

- C/L OLD RAILROAD GRADE SOUTH 9'
- SET NAIL & TAG OVER OLD NAIL IN E SIDE TWIN HICKORY S25E 25.84'
- SET NAIL & TAG OVER OLD NAIL IN W DIE 14" ASH N10E 5.80'
- NAIL & TAG IN SOUTH SIDE 14" ASH EAST 16.44'
- NAIL & TAG IN EAST SIDE 16" HICKORY SSE 48.60'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED MARCH 9, 1999
COUNTY REP. *Raymond E. Moored*

Raymond Moored

Date: 1/10/00

Surveyors License No. 26463

