

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>-2N</u> R <u>-12W</u>	F-13
	T _____ R _____	S $\frac{1}{4}$ Sec-33
	T _____ R _____	Watson Twp.
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBERO 007 PAGE 16

I, Basil Andress, in a field survey on December 10, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
West South Side Sec-33
40.00 Set Qr Sec Post
Elm 18 N69E 16
Elm 30 N66W 19

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd 5/8" Iron
In c/1 112th Ave +/-
c/1 19th St. to North is East 3.5' +/-

Replaced 5/8" iron w/std A.C. Mon (3/4" x 24" iron w/remon cap) and is accepted as a careful and faithful perpetuation of the position of the original corner

Approved by Allegan Co. Peer Group 8 December 1998

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED 12-8-1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Std A.C. Mon
- 16 d & Remon Tag SW Sde PP S 60° E 142.34'
 - 16 d & Remon Tag SE Sde 38" Oak N 55° E 48.71'
 - 16 d & Remon Tag SE Sde 38" Oak N 35° W 49.88'
 - 16 d & Remon Tag NW Sde PP S 50° W 106.37'
 - Std A.C. Mon (F-1, T-1N, R-12W) West 44.50'
 - In c/1 112th Ave (Gravel) +/-
 - c/1 19th St. (Gravel) to N is East 3.5' +/-
 - (F-13) to (E-13) AZ 269°-03'-35" 2637.89'
 - (F-13) to (G-13) AZ 89°-04'-37" 2636.50'



Signed by [Signature]
Surveyor's Michigan License No. 30075

Date 30 DEC 98