

**SURVEY  
REMONUMENTATION**

APR 20 1999

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>-2N</u> R <u>-12W</u>	<u>G-13</u>
	T _____ R _____	<u>SE Sec-33</u>
	T _____ R _____	<u>Watson Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED  
1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBRO 007 PAGE 17

I, Basil Andress, in a field survey on December 10, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
G.L.O.

West South Side Sec-34  
80.00 W. Oak 30 Cor Secs - 33 & 34

21 July 97 R.E. Moored, P.S.  
- Bndry Survey SW 1/4 Sec-34  
- Fd 5/8" iron No witnesses  
- (G-13) to (G-12) Meas 2651.68'  
- (G-13) to (H-13) Meas 2643.24'

21 Aug 69 D.A. Ratekin, C.S.  
- Bndry Survey in SE 1/4 Sec-33  
- Shows Cor No witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd  
Bent 3/4" iron  
G-1 (Fd 3/4" iron) West 43.50'

Replaced 3/4" iron w/std. A.C. Mon (3/4" x 24" iron w/remon cap) and is accepted as a careful and faithful perpetuation of the position of the original corner.

Approved by Allegan Co. Peer Group 8 December 1998

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY

DATE APPROVED 12-8-1998  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Std Allegan Co. Mon.  
- 16 d & Remon Tag NW Sde 6"-10"-10" Elm S 56.15'  
- 16 d & Remon Tag N'ly Sde PP S 65° W 125.05'  
- 16 d & Remon Tag SW Sde 6" Ash N 70° W 75.87'  
- 16 d & Remon Tag SE Sde 6"-12"-12" Oak N 40° W 41.14'  
- c/1 112th Ave. (Gravel) N 2' +/-  
- In line w/Occupation to N  
- Std A.C. Mon (G-1, T-1N, R-12W) East 43.50'  
- (G-13) to (F-13) AZ 269-04-37 2636.50'



Signed by [Signature] Date 30 Dec 98  
Surveyor's Michigan License No. 30075