

CAR 07 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY
Raymond E. Moored

00 FEB - 1 AM 8:53

FILED

LIBRARY / PAPER 51

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T. 2N R. 12W	H-13
SOUTH 1/4 POST SECTION 34, T.2N., R.12W. WATSON TWP.	T..... R.....
	T..... R.....
	T..... R.....
2. Property Controlling in section	S..... T..... R.....
	S..... T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R.....
4. Lot No. Recorded Plat.....		
5. Private Claims.....		

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Raymond Moored in a field survey on Dec 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO
WEST SOUTH SIDE SEC-34
40.00 SET QR SEC POST
BEECH 11 N36E 16
ELM 10 N51W 38
- R.E. MOORED, P.S., JULY 1997
BNDRY SURVEY SW 1/4 SEC-34
G-13 TO H-13 MEASURES 2643.24'

NO OTHER CORNER INFORMATION FOUND

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED MARCH 9, 1999
COUNTY REP. *Raymond E. Moored*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PAINTED 1/2" IRON (16" DEEP) MEAS. 2643.30' TO G-13 (MOORED MEAS. 2643.24'). REMOVED FOUND CORNER AND SET STD. ALLEGAN COUNTY REMON IRON WITH CAP.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMON PEER GROUP ON MARCH 9, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP

- NAIL & TAG IN NW SIDE 24" OAK S56W 63.00'
- NAIL & TAG IN E SIDE 18" OAK S20E 59.00'
- NAIL & TAG IN SQUARE FENCE POST N16E 29.55'
- NAIL & TAG IN SQUARE FENCE POST N21W 31.20'
- H-1, T1N, R12W WEST 46.50'

Raymond Moored

Date 1/11/00

Surveyors License No. 26463

