

MAR 07 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS ALLEGAN COUNTY
Singer L. Carter

00 FEB -1 AM 8:53

FILED
LIBERO 007 PAGE 58

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T. 2N R. 12W	I-13
SE COR. SEC. 34	T..... R.....
SW COR. SEC. 35	T..... R.....
T.2N., R.12W.	T..... R.....
WATSON TWP.	T..... R.....
2. Property Controlling in section	S.....T.....R.....
	S.....T.....R.....
3. Miscellaneous Property in Sec.	S.....T.....R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Raymond Moored in a field survey on Dec 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO
WEST SOUTH SIDE SEC-35
80.00 BEECH 5 COR TREE TO SEC'S 34 & 35
- D.A. RATEKIN, C.S., DATED 1969, WITNESS CARD
SET 1" IRON
ST. SIGN S 22.15'
PP NE 79.9'
14" CEDAR ENE 91.95'
SE COR HSE NW 97.70'
1" IRON WEST 49.50'
- J.M. BUDRIK, P.S., FEB. 1975
L.C.R.C., L.002 P.368
PART C: SET IRON ROD W/CAP
-PP
-14" CEDAR ENE 91.95'
-SE COR HSE NW 97.7'
-NE COR SEC 3, T.1N., R.12W. WEST 49.52'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED MARCH 9, 1999
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON WITH DAMAGED CAP IN MON BOX WITH COVER IN UPSIDE DOWN PER NO. 4 ABOVE.
SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND CORNER
ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY THE ALLEGAN COUNTY REMON PEER GROUP ON MARCH 9, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD 3/4" X 36" ALLEGAN COUNTY REMON IRON AND CAP
- NAIL & TAG IN NW SIDE POWER POLE N68E 83.00'
- NAIL & TAG IN NE SIDE 14" MAPLE N45W 54.05'
- NAIL & TAG IN N SIDE POWER POLE S64E 158.24'
- TOP C/L TCB S70W 93.95'
- +1, T1N, R12W WEST 49.52'
- SE COR HOUSE N50W 97.70'

[Signature of Raymond Moored]

Date 1/11/00

Surveyors License No. 26463

