

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ALLEGAN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>1</u> N R <u>11</u> W	<u>A-1 (NW,6)</u>
	T ___ R ___	<u>Gua Plain</u>
	T <u>2N</u> R <u>11W</u>	<u>A-13</u>
	T ___ R ___	<u>MARTIN</u>
2. Property Controlling in Section	S ___ T <u>1N</u> R <u>12W</u>	<u>M-1</u>
	S ___ T ___ R ___	<u>CTSEGO</u>
3. Miscellaneous Property in Sec.	S ___ T <u>2N</u> R <u>12W</u>	<u>M-13</u>
	S ___ T ___ R ___	<u>WATSON</u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1993 DEC 30 PM 2:47
REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN
Register of Deeds Stamp & File Number
FILED

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David F. Peabody, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. (Stone) Donald Ratekin (County Surveyor) 1973
Maple 14 NE 49.4' Stone W/Cross
T. Pole N30°W 52.87'
MSHD (1957) 26" Maple N18°W 44.40'
Stone X, Axe Bit 31" Maple N66°E 50.50'
23" Maple N18W 43.87' In line W/ fence to S.
16" Walnut S32E 30.24' P.P. SE 39.60'
28" Maple N66E 49.68' LCRC L.02, P.129

SURVEY &
REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Stone (Top part had been chipped off)
Maple 14 NE 49.4'
26" Maple N18°W 44.40'
31" Maple N66°E 50.50' (appears to be same from G.L.O.)
T. Pole N30°W 52.87'
P.P. SE 39.60'
This Corner is accepted as a careful and faithful perpetuation of the position of the Original Corner.

NOV 11 1993
CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Removed Stone And Placed 3/4" iron W/Remon Cap
Nail SW Side T. Pole N40°W 52.87'
20d Nail W/Allegan Co. Tag SW Side 32" Maple N18°W 43.82'
20d Nail SW Side Power Pole S37°E 39.38'
20d Nail W/Allegan Co. Tag W. Side 12" Elm S15°W 23.15'
3'± E. of Brush line South
28'± SE of C.L. Gravel Road



Signed by David F. Peabody Date 12/20/93
Surveyor's Michigan License No. 25866

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 24, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 004 page 267