

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>13W</u>	<u>A-1 (NW-Cor-Sec-6)</u>
	T _____ R _____	<u>Allegan-Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 30 PM 2:42  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICHIGAN  
*James A. LeBette*  
**FILED**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David R. Greer, in a field survey on December-16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- A-1  
Government Notes - 1831  
Post  
Beech 6" S26°W 4 links  
Beech 8" N76°E 5 links


SURVEY &  
REMONUMENTATION  
MAR 16 1994  
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-1  
Found steel bar in monument box over culvert and replaced steel bar with A.C. Remonumentation iron and cap and accepted it as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-1  
A.C. Remonumentation Iron & Cap in Monument Box over Culvert  
Set A.C. Remon nail & tag in NE Side 12" Ash AZ. 328°40' 67.27'  
Set A.C. Remon nail & tag in N Side Tri 10" Ash AZ. 292°30' 69.22'  
Set A.C. Remon nail & tag in S Side 26" Hickory AZ. 270°12' 152.29'  
NE Cor House Foundation AZ. 107°09' 201.22'  
Set A.C. Remon nail & tag in N Side Power Pole AZ. 90°07' 177.62'  
A-2 (W 1/4 Cor Sec 6) AZ. 180°00'



Signed by David R. Greer Date 12/16/93  
Surveyor's Michigan License No. 16042