

MAR 07 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

FILED

00 FEB -1 AM 8:35

Jayne A. Britte

REGISTER OF DEEDS
ALLEGAN COUNTY MICH.

REGISTER OF DEEDS STAMP & FILE NUMBER

FOR CORNERS IN: ALLEGAN COUNTY

LOCATED IN: CORNER CODE #

1. Public Land Survey T...2N R...13W A-5 ✓
 SW CORNER, SEC. 7
 NW CORNER, SEC. 18
 ALLEGAN TOWNSHIP T...2N R...14W M-5
 SE CORNER, SEC. 12
 NE CORNER, SEC. 13
 VALLEY TOWNSHIP T..... R.....
 T..... R.....

2. Property Controlling in section S.....T.....R.....
 S.....T.....R.....

3. Miscellaneous Property in Sec. S.....T.....R.....

4. Lot No.....Recorded Plat.....

5. Private Claims.....

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	-	5	-	4	-	3	-	2	-	1		
3													
4	7	-	6	-	9	-	10	-	11	-	12		
5													
6	16	-	17	-	16	-	15	-	14	-	13		
7													
8	19	-	20	-	21	-	22	-	23	-	24		
9													
10	30	-	29	-	28	-	27	-	26	-	25		
11													
12	31	-	32	-	33	-	34	-	35	-	36		
13													

I, Raymond Moored in a field survey on Nov. 7, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED Nov. 9, 1999
 COUNTY REP. *[Signature]*

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. (A-5)
WEST BTWN SEC'S 7 & 18
80.0 TO W BNDRY AT POST
- RATEKIN WITNESS CARD
SW COR SEC-7, ALLEGAN TWP
IRON A-5 TO A-4 = 2629.1'
- APR. 72, D.A. RATEKIN, C.S., L.C.R.C. LIBER 001, PAGE 235
1/2" IRON
-NW COR HSE FND S80°E 72.3'
-SW COR HSE FND S55°E 86.3'
-24" MAPLE S45°E 90.4'
-28" MAPLE S35°E 75.2'
- H.E.I. WITNESS CARD
1/2" IRON
-NW COR HSE FNDN S80E 72.30
-SW COR HSE FNDN S55E 86.30
-24" MAPLE S45E 90.40
-28" MAPLE S35E 75.20

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1/2" IRON W/ CAP (NO. 30075) IN MONUMENT BOX PER WITNESSES IN NO. 3 & 4 ABOVE. REMOVED IRON AND SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP IN MON BOX. MEASURED TO A-4= 2628.30' (PREV 2629.1'). ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON Nov. 9, 1999

TOTAL DISTANCE TRAVERSED= 2628.30' ON ROAD

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD 3/4" X 24 ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX
- IN LINE WITH OCCUPATION LINE TO WEST
 - C/L N & S ROAD EAST 1.4'
 - FD DBL HEAD NAIL IN SW FACE 6" POPLAR N40W 55.70'
 - FD DBL HEAD NAIL IN W FACE 38" MAPLE S25E 75.56'
 - NW COR HSE FNDN S75E 111.18'
 - FD MAG NAIL IN E FACE 8" MULBERRY S30W 48.96'
 - FD DBL HEAD NAIL IN W FACE 38" MAPLE S40E 91.73'

Raymond Moored Date 11/10/99

Surveyors License No. 26463

