

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

MAR 1 1993

For corners in

Allegan (County)

Located In:

Corner Code #

- |                                    |                            |                          |
|------------------------------------|----------------------------|--------------------------|
| 1. Public Land Survey              | T <u>2N.</u> R <u>13W.</u> | <u>B-1 (N 1/4 Sec 6)</u> |
|                                    | T _____ R _____            | <u>Allegan Twp.</u>      |
|                                    | T _____ R _____            | _____                    |
|                                    | T _____ R _____            | _____                    |
| 2. Property Controlling in Section | S _____ T _____ R _____    | _____                    |
|                                    | S _____ T _____ R _____    | _____                    |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____    | _____                    |
|                                    | S _____ T _____ R _____    | _____                    |

1993 DEC 30 PM 2:46  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 J. J. Blatter  
 FILED  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, David R. Greer, in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:


B-1  
 This corner not set by the Government.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1  
 Set A.C. Remonumentation Iron & Cap at proportioned distance between A-1 and C-1 and on the South line of Section 31, Town 3 North, Range 13 West. This position no established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-1  
 A.C. Remonumentation iron & cap on South line of Section 31, T3N, R13W
- |  |             |        |
|--|-------------|--------|
| Set A.C. Remon tag & nail in NE Side 18" Oak   | AZ. 312°25' | 58.04' |
| Set A.C. Remon tag & nail in S Side 14" Oak    | AZ. 79°23'  | 42.54' |
| Set A.C. Remon tag & nail in SW Side 10" Beech | AZ. 129°22' | 65.35' |
| Set A.C. Remon tag & nail in N Side 16" Maple  | AZ. 254°37' | 86.80' |
| Set A.C. Remon tag & nail in E Side 12" Oak    | AZ. 7°55'   | 5.46'  |
| CL Maple Trees to North                        | AZ. W       | 43.00' |
| E-W Fence Line                                 | N           | 0'     |



Signed by David R. Greer Date 12/16/93  
 Surveyor's Michigan License No. 16042

W:\Dcl\Serv\Forms.doc

LIBER 004 page 353

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983