

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>13W</u>	B-13 (S 1/4, 31)
	T _____ R _____	ALLEGAN TWP.
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

1993 DEC 30 PM 2:41
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
Basil J. Address

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BASIL ADDRESS, in a field survey on OCTOBER 29, 1993
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O.
 -WEST SOUTH SIDE SEC-31, T-2N, R-13W
 -40.00 CHS. (2640') SET QR. SEC POST
 -WITNESSES: BEECH 9" N 5 E 33 LKS. (21.78')
 BEECH 12" N 86 W 31 LKS. (20.46')


THERE ARE NO AVAILABLE RECORDS OF THIS CORNER EVER BEING PERPETUATED OR REESTABLISHED, AFTER BEING SET BY THE ORIGINAL GOVERNMENT SURVEYORS.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 SET STD. A. C. MONUMENT BY USING EXISTING PHYSICAL EVIDENCE.
 -SET IN E & W FENCE LINE
 -236.94' EAST OF AN OCCUPATION LINE (LG. TREES & OLD FE) TO SOUTH (N&S 1/4 LINE, SEC-6)
 -THIS DISTANCE WAS THE GOVT. JOG AT THE NE COR. OF THE SECTION
 -BY SETTING THE CORNER AT THE ABOVE JOG DISTANCE, WE FIT EXISTING 1/8 TH. LINE FENCES.

THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP 10-26-93.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET STD. A. C. MONUMENT (3/4" STEEL PIN & REMON. CAP) 1' +/- DEEP (IN FIELD DR.)
 NAIL & REMON. WASHER N SDE 26" ELM EAST 94.22'
 NAIL & REMON. WASHER SW SDE 6" ELM SE 158.36'
 NAIL & REMON. WASHER N SDE TWIN 14" & 18" W. CHERRY WEST 60.57'
 (NAILS AND WASHERS ARE 5 1/2' +/- ABOVE GROUND)
 N 1/4 SEC-5, T-1N, R-13W (STD. A. C. MON.) WEST 236.94'



Signed by Basil J. Address Date 20 DEC 93
 Surveyor's Michigan License No. 36075