

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
COMMISSION
Allegan (County)

Located in: _____ Corner Code # _____

1. Public Land Survey T 2N R 13W — C-1 (NW-Cor-Sec 6)
T _____ R _____ — Allegan Twp.
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

1993 DEC 30 PM 2:45
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
Register of Deeds Stamp & File Number
FILED

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David R. Greer, in a field survey on December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1
Government Notes 1831
Post
Ironwood 6" S82°W 20 links NE Cor RR tie fence cor post W 14.56'
W Wood 18" S82°E 14 links NE Cor RR tie fence brace post N60°W 16.35'
SE Root 32" Maple S75°W 18.36'
E Root 14" Cherry knee high S10°W 34.06'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1
Found steel bar and replaced it with A.C. Remonumentation Iron & Cap and accepted it as a careful and faithful perpetuation of the position of the original corner
Nail in NE Cor RR tie fence corner post W 14.56'
Nail in NE Cor RR tie fence corner brace post N60°W 16.35'
Nail in SE root 32" maple S75°W 18.36'
Nail in E root 14" cherry about knee high S10°W 34.06'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1
A.C. Remonumentation Iron & Cap on South line, Section 32, T3N, R13
Found Nail in SE Side 34" Maple AZ. 247°46' 19.20'
Set A.C. Remon tag & nail in W Side 14" Cherry AZ. 193°14' 34.24'
Set A.C. Remon tag & nail in SW Side 10" Cherry AZ. 308°02' 41.50'
Set A.C. Remon tag & nail in NW Side 6" Cherry AZ. 46°19' 11.36'
CL RR tie fence post, fence N, S, W AZ. 270°00' 14.84'
A.C. Remon Iron B-1(N1/4 Sec 6 T2N, R13W) AZ. 270°00'



Signed by David R. Greer Date Dec. 16, 1993
Surveyor's Michigan License No. 16042

W3DecalSert1Remon.doc

LIBER 004 PAGE 352

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 22, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983