

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
 For corners in  
 ALLEGAN  
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>13W</u>	C-13(SE, 31) ALLEGAN TWP.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1993 DEC 30 PM 2:41  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 Register of Deeds Stamp & File Number  
 FILED

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, BASIL ANDRESS in a field survey on OCTOBER 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O.

- WEST SOUTH SIDE SEC.-32, T-2N, R-13W
- 80.00 CHS. (5280') SET POST COR. SECTIONS 31 & 32
- WITNESSES: BEECH 8" N 15 E 32 LKS. (21.12')
- BEECH 10" N 47 W 28 LKS. (18.48')

OLD NOTES (COUNTY SURVEYOR)

- STONE, WITNESS: MAPLE 20" NW 76.6'

L.C.R.C. L-2, P-177

FD. 1" PIPE

16" ELM NE 65.7'

32" ASH N 70 W

12" ASH N 35 E 44.4'

75.5'

10" W CHERRY EAST 27.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FD. 3/4" PIPE ON SIDE OF LARGE FLAT STONE  
 SET STD. A. C. MON. IN 3/4" PIPE

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP 10-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STD. A. C. MONUMENT (3/4" STEEL PIN & REMON. CAP)
- NAIL & REMON. WASHER NE SDE 8" ASH SOUTH 1.41'
- NAIL & REMON. WASHER SW ROOT 44" ASH WNW 75.86'
- NAIL & REMON. WASHER W ROOT 30" ASH NE 43.61'
- NAIL & REMON. WASHER N SDE 12" HICKORY ENE 27.21'
- NAIL & REMON. WASHER N SDE 10" ASH ESE 9.51'
- NAIL & REMON. WASHER NW SDE TWIN 7" ASHES SW 4.59'
- IN LINE WITH C/L 34TH. ST. TO NORTH
- C/L 34TH. ST. WEST 28.4' +/-



Signed by Basil J. Andress, Jr. Date 20 DEC 93  
 Surveyor's Michigan License No. 30075