

SURVEY & REMONUMENTATION

APR 29 1996

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners of **COMMISSION**

ALLEGAN <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T 2N R 13W	D-13
	T _____ R _____	ALLEGAN
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

1995 DEC 14 PM 2:32

Register of Deeds Stamp & File Number

REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DONALD R. PITTS JR. in a field survey on JULY 27, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. SET POST
BEECH 9 N39E 48
BEECH 16 N31W 12

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


NO PHYSICAL CORNER FOUND
SET STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP #23520 ON EXTENSION C-13, T2N, R13W D-1, T1N, R13W, EQUIDISTANT C-13 TO E-13, T2N, R13W.
TRAVERSED 5242' EAST AND 2620' WEST
APPROVED BY THE ALLEGAN CO. REMON PEER GROUP JUNE 13, 1995, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 4-13-95
COUNTY REP. Ant. J. Van Cester

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP # 23520
D-1 T1N, R13W STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP #23520 WEST 210.69'
NAIL & REMON TAG S SIDE 10" MAPLE 2.74'
NAIL & REMON TAG NE SIDE 10" OAK S 45° E 35.78'
NAIL & REMON TAG S SIDE 8" CHERRY S 85° E 32.74'

Signed by Donald R. Pitts Jr. Date 29 August 1995
Surveyor's Michigan License No. 25867



0005 PAGE 177