

REC'D

APR 9 1998

SECTION

ALLEGAN CO. REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Allegan County

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

LIBR0006 PAGE333

<u>ALLEGAN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T-2N R-13W	E-2
	T____R____	E1/4 SEC. 5
	T____R____	ALLEGAN TWP
	T____R____	_____
2. Property Controlling in Section	S____T____	_____
	S____T____	_____
3. Miscellaneous Property in Sec.	S____T____	_____
	S____T____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, ARTHUR W. BRINTNALL, in a field survey on 27 AUG 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5	⊕	4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
NORTH BETN SECS 4 & 5  
40.00 SET QR SEC POST  
BEECH 4 S 54 E 8  
SUGAR 9 S 65 W 8

NOV 9, 1889 J.W. HICKS, C.S.  
40.38 (2665.08) W TO D-2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FD FE COR
- FE N-S-W
- 268°-33'43" 2664.08 TO D-2 (STD A.C. MON)
- 177°-24'57" 2630.77 TO E-3 (STD A.C. MON)
- 358°-01'35" 1599.50 TO E-1-2 SEQ #3 (STD A.C. MON)

SET STD A.C. MON (3/4" X 36" IRON WITH CAP) @ FE COR

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

APPROVED BY ALLEGAN PEER GROUP 11 AUG 98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- STD A.C. MON (3/4" X 36" IRON WITH CAP)
- IN LINE WITH FE TO N-S-W
- NAIL & REMON TAG SE SDE 14" W. CHERRY N 45° E 9.64'
- NAIL & REMON TAG N SDE 12" ASH S 50° E 14.38
- NAIL & REMON TAG W SDE 10" SASSAFRAS SOUTH 16.70'
- NAIL & REMON TAG NE SDE 12" W CHERRY N 45° W 17.98'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY

DATE APPROVED AUG 11, 1998  
COUNTY REP. John T. Van Oosterhout

Signed by Arthur W. Brintnall  
PREIN&NEWHOF  
Surveyor's Michigan License No. #28407

Date SEPT 8, 1998



