

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

ALLEGAN
(County)

Located in:

Corner Code #

		2N	13W	E-3 ALLEGAN TWP
1. Public Land Survey	T	R		
SEC. COR. COMMON TO	T	R		
SEC. 4, 5, 8, 9, T2N, R13W,	T	R		
	T	R		
2. Property Controlling	S	T	R	
in Section	S	T	R	
3. Miscellaneous	S	T	R	
Property in Sec.	S	T	R	

REGISTERED
 ALLEGAN COUNTY
 97 JAN 22 PM 1:14
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, RAYMOND MOORED, in a field survey on OCT, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY


APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-26-96
 COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON IN MON BOX PER ACCESSORIES LISTED ABOVE. REPLACED WITH 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP. APPROVED BY ALLEGAN COUNTY REMON PEER GROUP 11-26-96, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.		
NAIL & TAG IN W. SIDE R.R. TIE FENCE POST (N & S FENCE)	NORTH	35.63'
NAIL & TAG IN W. SIDE 6" ELM	S30°E	34.99'
N. FACE OF UNDERGROUND TELE. CABLE BOX	S45°W	38.41'
E. FACE OF NO PASSING ZONE SIGN	N75°W	142.42'
NAIL & TAG IN 12" ELM	S70°W	149.34'



Signed by [Signature]
 Surveyor's Michigan License No. 26463

Date 12/13/96

0005 PAGE 344

GOVERNMENT CORNER HISTORY

SEC. COR. COMMON TO SEC. 4, 5, 8, 9
TOWN 2 NORTH, RANGE 13 WEST

E-3

G.L.O		NORTH 80.00 CHAINS BETWEEN SEC 8 & 9 SET POST COMM TO SEC 4, 5, 8, 9, BEECH 6 N54°W 28 BEECH 6 S54°E 20
HICKS	1870	COUNTY SURVEYOR NOTES SURVEY OF SECTION 5 STONE "X" EAST TO N 1/4 COR SECTION 9, EAST 40.05 1/2 CHS
RATEKIN (SEC. CARD)		SHOWS NOTHING FOR CORNER.
RATEKIN	1973	SURVEY, LIBER 842 PAGE 98 1" IRON IN MON BOX C/L 122ND 1' SOUTH IN LINE WITH FENCE TO NORTH S. END 18" CMP S20°W 35.75' NAIL IN ASH SOUTH 55.45'
RATEKIN	1975	SURVEY, LIBER 899 PAGE 269 SAME WITNESSES AS SURVEY IN 1973