

SURVEY & REMONUMENTATION

2 ✓
9-
2-

APR 07 1998

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>ALLEGAN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T-3N R-13W	G-13
	T R	SW 34
	T R	MONTEREY TWP
2. Property Controlling in Section	T-2N R-13W	G-1
	S T R	NW 3
	S T R	ALLEGAN TWP
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
James L. Ecker

98 JAN 21 PM 1:17

FILED

Register of Deeds Stamp & File Number

I, ARTHUR W. BRINTNALL, in a field survey on 17 OCT 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	N
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-13 (T 3N, R13W)	AUG 20, 1869 J.W. HICKS, CO SURVEYOR
G.L.O.	SURVEY OF SE 1/4 SEC-33
WEST SOUTH SIDE SEC-34, T-3N, R-13W	(2662.44') 40.34 NORTH TO E 1/4 COR
80.00 SET POST CORNER SECS 33 & 34	
TAMARACK 15 N86E 42	
TAMARACK 14 N82W 37	G-13 & G-1 ARE COMMON

CONT. ON BACK OF CERTIFICATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 & G-1
 FD 3/4" IRON
 - 16D N SDE 6" ALDER WEST 7.83'
 - 16D W SDE 12" ELM NORTH 12.87'
 - 16D E SDE 14" ELM SOUTH 25.56'
 - 16D NE 20" TAMARACK NW 68.13'
 - IN LINE WITH OLD DOWN FE TO N & W


APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 10-14-97
 COUNTY REP. K.V.O.

REPLACED WITH STD ALLEGAN CO. MON. (3/4"x36" IRON WITH CAP) AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN CO. PEER GROUP 14 OCT 97

C. Description of monument for corner and accessories established to perpetuate locating the position of this corner:

G-1 & G-13
 STD ALLEGAN CO. MON (3/4"x36" IRON W/CAP)
 - 16D & REMON TAG N SDE 6" ALDER WEST 7.85'
 - 16D & REMON TAG W SDE 12" ELM NORTH 12.85'
 - 16D & REMON TAG E SDE 14" ELM SOUTH 25.54'
 - 16D & REMON TAG E ROOT 20" TAMARACK N40°W 67.00'
 - IN LINE W/ OLD DOWN FE TO N & W



Signed by Arthur W. Brintnall Date Oct 29, 1997

PREIN & NEWHOF #28407
 Surveyor's Michigan License No. _____

USE 0006

G-1 ALLEGAN
G-13 MONTEREY (CONTINUED)

REF: 0006 PAGE 017

JUNE 13, 1968 D.A. RATEKIN, C.S.

SET 1" IRON IN FE COR
FE N & W
NAIL N SDE 3" ALDER W 7.85'
NAIL E SDE 3" ELM N 12.70'
NAIL NE SDE 10" TAMARACK N45°W 68.30'

AUG 28, 1974 D.A. RATEKIN, C.S.

ACT 132 SURVEY L , P
IRON IN FE COR
FE N & W
3" ALDER 7.85'
3" ELM N 12.70'
10" TAMARACK N45°W 68.30

NOV 8, 1974 D.A. RATEKIN, C.S.

L.C.R.C. L-003, P.15
SAME WITNESSES AS ACT-132 SURVEY

JAN 22, 1993 K.L. VAN ORDER, C.S.

FD 1" IRON
3" ALDER W 7.85
9" ELM N 12.87
10" ELM S 25.56
18" TAMARACK NW 68.13
DIST BETWEEN G-12 & G-13 OF 2662.00'

DEC 12, 1994 D.R. PITTS, P.S.

SURVEY IN SE 1/4 SEC-33
1331.07' NORTH TO E 1/8 POST SE 1/4

G-1 (T2N, R13W) ALLEGAN TWP

G.L.O.

NORTH BTWN SECS 3 & 4
82.26 TO NORTH BNDRY AT POST
COMMON WITH G-13 T-3N, R-13W
MONTEREY TWP