

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

1995 DEC 14 11 2:32
 Register of Deeds Stamp & File Number
 F I I F D

For corners in
ALLEGAN (County) Located in: Corner Code ##

1. Public Land Survey	T <u>2N</u> R <u>13W</u>	<u>G-13</u>
	T _____ R _____	<u>ALLEGAN</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	10	9	8	7	6	5	4	3	2	1		
7												
8	19	18	17	16	15	14	13	12	11	10	9	8
9												
10	30	29	28	27	26	25	24	23	22	21	20	19
11												
12	31	32	33	34	35	36						
13												

DONALD R. PITTS JR., in a field survey on JULY 27, 1995
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. SET POST
- SUGAR 18 N31E 30
- SUGAR 24 N65W 29
- 1983 COUNTY SURVEYORS NOTES
- SET 1/2" PIPE 5/9/83
- P.K. SW ROOT 27" HACKBERRY N50W 11.10'
- P.K. E SIDE 21" WALNUT N20W 19.94'
- P.K. E SIDE 5" HICKORY NORTH 6.03'
- 1/2" PIPE WEST 75.90'

(CONTINUED ON BACK OF CERTIFICATE)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 1/2" REBAR W/CAP "D.E.E. 29245"
- N & T IN E OF 14" ELM S 25 E 44.30'
- N & T IN E OF 14" SYCAMORE S 10 W 33.93'
- N & T IN NE OF 12" ELM S 50 E 59.00 FEET
- PULLED REBAR AND SET STANDARD ALLEGAN CO. REMON 3/4" x 36" IRON W/RED CAP # 23520 TRAVERSED 8070' WEST
- APPROVED BY THE ALLEGAN CO. REMON PEER GROUP JUNE 13, 1995, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 6-13-95
 COUNTY REP. Donald R. Pitts Jr.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-1 T1N, R13W - STANDARD ALLEGAN CO. REMON. 3/4" x 36" IRON W/RED CAP # 23520 WEST 75.85'
- FOUND 1/2" REBAR W/PLASTIC CAP "DEE 29245"
- N & T IN E OF 14" ELM S 25 E 44.30'
- N & T IN E OF 14" SYCAMORE S 10 W 33.93'
- N & T IN NE OF 12" ELM S 50 E 59.00'



Signed by Donald R. Pitts Jr. Date 29 AUGUST 1995
 Surveyor's Michigan License No. 25867

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

(CONTINUED FROM FRONT OF CERTIFICATE)

A. 1994 - DAVID E. ERICKSON
L.C.R.C. LIBER 4, PAGE 388
SET 1/2" REBAR W/PLASTIC CAP "DEE 29245"
SET N & T IN E OF 14" ELM S 25 E 44.30'
SET N & T IN E OF 14" SYCAMORE S10E 33.93'
SET N & T IN NE OF 12" ELM S 50 E 59.00'
CAPPED IRON N.E. COR. SEC 4 N 85 W 75.90'
FOUND CAPPED IRON # 26463 NORTH 50.21'