

FILED

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

00 FEB -1 AM 0:35

FOR CORNERS IN: ALLEGAN COUNTY

LOCATED IN: T. 2N R. 13W CORNER CODE # J-1

1. Public Land Survey NORTH 1/4 COR. SECTION 2, T.2N., R.13W. ALLEGAN TOWNSHIP

2. Property Controlling in section

3. Miscellaneous Property in Sec.

4. Lot No., Recorded Plat.

5. Private Claims.

Joyce A. Ortle
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Nov. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O.
NOT ESTABLISHED BY G.L.O.
- MITCHELL SURVEYS INC., 9-28-93, FIELD NOTES FROM JOB# 93-982
FD. 3" ROUND PIPE W/2" SQ TOP
NAIL IN S. SIDE 6" ELM S20°E 6.76
FD. NAIL N.W. SIDE 8" ASH S40°W 10.74
FD. NAIL S. SIDE 10" MAPLE N40°W 22.65
NIAL E. SIDE 8" BASSWOOD N5°E 13.46
IN OLD FENCE E-W SOUTH

SURVEY &
RECORDATION

MAR 07 2000

SECTION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3" PIPE PER NO. 2 ABOVE. CORNER AS FOUND IS ON RANGE LINE AND 0.03' OFF SPLIT OF DISTANCE FOR MILE BETWEEN I-1 AND K-1. SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND CORNER AND ACCEPTED POSITION AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED BY THE ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON DEC. 14, 1999

TOTAL OFF ROAD TRAVERSING: 5307.39'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 14, 1999.
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" x 36" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

- NAIL & TAG IN W SIDE 14" POPLAR N5E 22.80'
- NAIL & TAG IN S SIDE 8" ASH N85W 10.85'
- NAIL & TAG IN N. SIDE 14" ASH S70W 19.51'
- NAIL & TAG IN SE SIDE 6" OAK S30E 6.75'
- J-13, T3N, R13W EAST 1.68'

Raymond Moored Date 1/10/00

Surveyors License No. 26463

