

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>ALLEGAN</u> <small>(County)</small>	Located In.	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>13W</u>	<u>I-3</u>
	T _____ R _____	<u>ALLEGAN</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 1995 DEC 14 P.M. 2:32
 FILED

Register of Deeds Stamp & File Number

**SURVEY &
REMONUMENTATION
COMMISSION**

APR 29 1996

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DONALD R. PITTS JR., in a field survey on SEPTEMBER 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. WEST CORRECTED BETWEEN SECTIONS 1 AND 12 40.00 SET POST
 W. ASH 24 S 15 E 16
 BEECH 7 N 4 E 13
 1870 J.W. HICKS, COUNTY SURVEYOR
 STONE CROSS ON N & S
 NO WITNESSES
 1961 DON ALLEN, COUNTY SURVEYOR
 BAY VIEW PLAT, LIBER 8 OF PLATS, PAGE 17
 1971 DONALD A. RATEKIN, COUNTY SURVEYOR

(CONTINUED ON BACK OF CERTIFICATE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 1 1/2" IRON IN MON BOX
 TELEPHONE POLE N 60°E 69.2'
 CENTERLINE INTERSECTION EAST 7'
 PULLED IRON AND SET STANDARD ALLEGAN CO. REMON 3/4" x 24" IRON IN MON BOX.
 APPROVED BY ALLEGAN CO. REMON PEER GROUP ON SEPTEMBER 12, 1995 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY

DATE APPROVED 9-12-95
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD ALLEGAN CO. 3/4" x 24" IRON W/RED CAP # 23520 IN MON BOX,
 NAIL & REMON TAG W SIDE 18" OAK SOUTH 71.91'
 NAIL & REMON TAG NW SIDE TELEPHONE POLE N 65°E 69.51'
 NAIL & REMON TAG NE SIDE 6" PINE S 50°E 143.98'
 S. SIDE STOP SIGN/STREET SIGN N 10° W 40.70'



Signed by Donald R. Pitts Jr. Date 22 September 1995
 Surveyor's Michigan License No. 25867

USE: 0005 PAGE 188

SHEET 1 OF 2

(CONTINUED FROM FRONT OF CERTIFICATE)

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION .

L.C.R.C. LIBER 1, PAGE 74
FOUND 3/4" PIPE
TELEPHONE POLE N 60°E 69.2'
SHEILD SIGN POST S 20°E 29.7'
4" IRON PIPE SOUTH 33.5'
TELEPHONE CABLE MARKER N 75°W 85.55'
CENTERLINE INTERSECTION EAST 7'

1972 DONALD A. RATEKIN, COUNTY SURVEYOR
RECORDED SURVEY LIBER 811, PAGE 376
PIPE
SAME WITNESSES AS L.C.R.C. LIBER 1, PAGE 74