

FILED

Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FEB -1 AM 8:35

LIBRARY 07 LABEL 18

For corners in  
Allegan  
(County)

Located In: Corner Code #

1. Public Land Survey T2N R. 13W M-8 (E 1/4 25)  
T R Allegan Twp.  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

*Joyce A. Carter*  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Steven Koerber, in a field survey on October 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-8 1831 GLO-L. Lyon DS  
Set corner  
Elm 18 S7W 42  
Do. 14 N6W 13

1. Old notes from notecard file  
Stone  
18" Elm SW 37'  
12" Walnut NW 84'

(Additional info. on back of sheet)

SURVEY &  
RECORDATION  
MAR 07 2000  
SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found 1" Solid rod in mon. box  
Twin 12" Walnut N60°E 45.4'  
Rerod North 26.42' (A-8 Watson Twp.)  
C/L highway North 1'± East  
On Tree row to West  
Set Standard Allegan Co. Mon. (3/4" x 24" Iron Rod with Remon.cap) at the position as occupied by the 1" solid rod in the mon. box.  
This corner is accepted as a careful and faithful perpetuation of the position of the original corner.  
Peer Group approval November 9, 1999.  
Dist to M-9 = 2654.86'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Set Standard Allegan Co. Mon. (3/4" x 24" Iron Rod with Remon.cap)  
Set nail & Allegan Co. Remon. tag in NW side 12' twin Walnut N60°E 45.95'  
Set nail & Allegan Co. Remon. tag in S. side P.Pole N80°E 118.42'  
Set nail & Allegan Co. Remon. tag in N. side 12" Walnut S80°W 34.07'  
NW corner house siding S70°E 152.67'  
On tree and fence line to West  
On centerline blacktop road



Signed by *[Signature]*  
Surveyor's Michigan License No. 39085

Date 12-15-1999

M-8 ALLEGAN TWP.

2. 10-30-1973  
L.C.R.C. Liber 2, Pg. 179  
Donald Ratekin  
Stone  
Dug for stone set 1" Iron from witness stumps  
12" Walnut N35°W 66.8'  
24" Walnut N25°W 126.4'  
4" Walnut (Nearest in clump) N60°E 45.5'
  
3. 11-28-1973  
Act 132 survey  
Liber 841, pg. 520  
Don Ratekin  
Same wits as No. 2 above
  
4. Survey dated 7-25-1973  
Don Ratekin  
1" Iron  
No wits
  
5. Wightman Moored notes  
No date  
Same wits as No. 2 above

SURVEY &  
REPRESENTATION

MAR 07 2000

SECTION

LIBERO 007 PAGE 149