

RF

BAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

Stephen A. Collins

00 FEB - 1 AM 8:51

FILED

LIBRARY / 1999

SECTION

FOR CORNERS IN: ALLEGAN COUNTY

LOCATED IN: T. 2N R. 14W CORNER CODE # A-11

1. Public Land Survey
S.W. CORNER SEC. 30, N.W. CORNER SEC. 31, T.2N., R.14W. VALLEY TOWNSHIP

2. Property Controlling in section

3. Miscellaneous Property in Sec.

4. Lot No., Recorded Plat.

5. Private Claims.

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. G.L.O.
WEST BETWEEN SEC'S 30 & 31
78.25 INTERSECT W. BOUNDARY 46 LKS S OF POST
& SET POST COR SEC'S 30 & 31 FROM WHICH
A W. OAK 10 IN DIA BEARS N78E 17LKS
A W. OAK 11 IN DIA BEARS S19E 21LKS

NO OTHER CORNER HISTORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/2" PIPE 0.47' EAST OF RANGE LINE AND 31.14' SOUTH OF FD. COR. AT M-11, T2N, R15W.
FOUND MDNR WITNESS TABS IN TREES AROUND CORNER.
SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP 0.47' WEST OF FOUND CORNER ON RANGE LINE.
HELD MEASURED JOG FROM FOUND CORNER AT M-11

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE ALLEGAN COUNTY REMON PEER GROUP ON DEC. 14, 1999

TOTAL ON ROAD TRAVERSING = 2631.75'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 14, 1999
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP
- FD MDNR NAIL & TAG IN NE SIDE 30" OAK S65E 28.52'
- FD MDNR NAIL & TAG IN NW SIDE 36" OAK S56W 26.23'
- FD MDNR NAIL & TAG IN SW SIDE 28" OAK S25E 58.23'
- FD MDNR NAIL & TAG IN NE SIDE 10" TW OAK N24W 50.00'
- M-11, T2N, R15W NORTH 31.14'
- C/L TWO TRACK ROAD TO EAST NORTH 13'+/-

Raymond Moored Date 12/24/99

Surveyors License No. 26463

