

MAR 07 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY
James A. Moore

00 FEB - 1 AM 8:51

LIBRARY / PAID 5.00
FILED

FOR CORNERS IN: ALLEGAN COUNTY

1. Public Land Survey
WEST 1/4 CORNER SECTION 31, VALLEY TOWNSHIP

LOCATED IN: T. 2N R. 14W

CORNER CODE # A-12

2. Property Controlling in section
S.....T.....R.....

3. Miscellaneous Property in Sec.
S.....T.....R.....

4. Lot No.....Recorded Plat.....

5. Private Claims.....

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Raymond Moored in a field survey on Aug. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NOT SET BY G.L.O.

NO OTHER CORNER HISTORY AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF ORIGINAL CORNER OR SUBSEQUENT RESTORATION.
SET STANDARD ALLEGAN COUNTY REMON IRON W/CAP ON LINE BETWEEN A-13 (M-13) AND M-11, T.2N., R.15W. AT 1/2 DISTANCE BETWEEN A-11 AND A-13. THIS POSITION FITS DITCH OCCUPATION LINE TO EAST.

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED BY THE ALLEGAN COUNTY REMON PEER GROUP ON DEC. 14, 1999

TOTAL ON ROAD TRAVERSING = 2631.75'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 14, 1999
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP

- 30" OAK, DNR TAB NNE SIDE S65°E 28.95'
- 36" OAK, DNR TAB NW SIDE S56°W 25.86'
- 28" OAK, DNR TAB SW SIDE S25°E 58.39'
- 10" TW OAK, DNR TAB NE SIDE NORTH 31.14'
- CLYDE TWP CORNER N24°W 49.78'
- C/L TWO TRACK TO EAST NORTH 13'+/-

Raymond Moored Date 12/24/99

Surveyors License No. 26463

